

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>13W</u>	<u>A-2</u>
	T _____ R _____	<u>Trowbridge Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:39  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 FILED

Register of Deeds Stamp & File Number

**SURVEY &  
 REMONUMENTATION**

APR 29 1996

COMMISSION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Donald R. Pitts Jr., in a field survey on April 1, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Not set by Government

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 4-12-94  
 COUNTY REP. Donald R. Pitts

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No Physical Monumnet Found and No previous history  
 Set Standard Allegan Co. Remon. 3/4" X 36" Iron with Red Cap #23520 on Range Line 42.24' North of M-2, T.1N., R.14W., corresponding with jog distance at S.W. Section 6, T.1N., R.13W., per G.L.O.  
 Approved by Allegan Co. Peer Group on April 12, 1994. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.  
 Traversed off road 2389' North and South 2685' South

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Standard Allegan Co. Remon. 3/4" X 36" Iron with Red Cap #23520 on West Edge of Drain.  
 M-2, T.1N., R.14W., Standard Allegan Co. Remon. 3/4" X 36" Iron with Red Cap #23520 South 42.2  
 Nail & Allegan Co. Remon. Tag W. Side 15" Maple South 0.87'  
 " " " " " " W.'ly Side 5" Hackberry S.30°W. 38.36'  
 " " " " " " E.'ly Side 4" Maple N.50°W. 26.01'  
 " " " " " " N.E.'ly Side 8" Poplar N.10°W. 57.78'



Signed by Donald R. Pitts Jr. Date 18 April 1995  
 Surveyor's Michigan License No. 25867

0005 PAGE 294