

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1N</u>	R	<u>13W</u>	<u>A-3</u>
	T		R		<u>TROWBRIDGE</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
Miscellaneous	S		T	R	
Property in Sec.	S		T	R	

**SURVEY &
 REMONUMENTATION**

APR 29 1995

COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

1995 DEC 14 PM 2:39
 ALLEGAN COUNTY REGISTER OF DEEDS

FILED

1. DONALD R. PITTS, JR. in a field survey on SEPTEMBER 7, 1995
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 77.18 TO W. BOUNDARY 64 LKS
 N OF POST & SET POST COR
 SECS 6 & 7
 BEECH 5 N 49 E 45
 BEECH 11 S 81 E 64
 1879 COUNTY SURVEYOR RECORDS
 STONE
 NO WITNESSES
 CIRCA 1900 COUNTY SURVEYOR RECORDS
 STONE MAPLE 12 S 57.4'

(CONTINUED ON BACK OF CERTIFICATE)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND REM IRON 42.84' NORTH OF M-3, T1N, R14W and 0.13' EAST OF TOWN LINE
 FOUND STONE 42.93' NORTH OF M-3, T 1 N, R 14 W 0.40' EAST OF TOWN LINE
 REMOVED STONE AND IRON
 SET STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP #23520 42.93' NORTH OF M-3, T1 N, R 14 W ON LINE M-3, TO M-2, T 1N, R 14 W.
 APPROVED BY THE ALLEGAN CO. REMON PEER GROUP ON SEPTEMBER 12, 1995 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 9-12-95
 COUNTY REP. Donald R. Pitts, Jr.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520
 NAIL & REMON TAG E SIDE 14" WALNUT CLUMP SOUTH 98.29'
 NAIL & REMON TAG SE SIDE 9" WALNUT S30°W 86.82'
 NAIL & REMON TAG E SIDE 6" W. CHERRY N25°W 95.41'
 M-3 T1N, R14W STANDARD ALLEGAN CO. 3/4" IRON W/RED CAP # 23520 SOUTH 42.93'
 CENTERLINE GRAVEL ROAD 110th AVE SOUTH 29'±



Signed by Donald R. Pitts, Jr.
 Surveyor's Michigan License No. 25867

Date 22 September 1995

0005 PAGE 295

SHEET 1 OF 2

(CONTINUED FROM REVERSE SIDE)

1980	DONALD A. RATEKIN COUNTY SURVEYOR RECORDS FOUND 1/2" IRON CL ROAD 29' S
1992	WIGHIMAN MOORED INC. FOUND CAPPED IRON M-3, T 1 N, R 14 W. SOUTH 42.24'