

RECORDED

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

*Joyce A. B...  
REGISTER OF DEEDS  
ALLEGAN COUNTY*

00 FEB -1 AM 8:51

FILED

LIBER 007 HARRY H U

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN: TROWBRIDGE TWP.	CORNER CODE #
1. Public Land Survey	T.1N... R....13W	A-12
	T..... R.....	.....
	T..... R.....	.....
	T..... R.....	.....
2. Property Controlling in section	S.....T.....R.....	.....
	S.....T.....R.....	.....
3. Miscellaneous Property in Sec.	S.....T.....R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	-	5	-	4	-	3	-	2	-	1		
3													
4	7	-	8	-	9	-	10	-	11	-	12		
5													
6	18	-	17	-	16	-	15	-	14	-	13		
7													
8	19	-	20	-	21	-	22	-	23	-	24		
9													
10	30	-	29	-	28	-	27	-	26	-	25		
11													
12	31	-	32	-	33	-	34	-	35	-	36		
13													

I, Raymond Moored in a field survey on Aug. 20, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- CORNER NOT SET BY G.L.O.
- CORNER ESTABLISHED BY HUGH MAC DOUGALL 3-31-1911  
SET COR FROM E 1/4 COR  
SEC 36, T1N, R14W - NO WITS

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC. 14, 1999  
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION  
ESTABLISHED CORNER POSITION ON LINE BETWEEN M-12 AND M-11, T.1N., R.14W.  
AT 1/2 THE MEASURE JOG AT A-11 AND M-11. (60.98'). M-12 SOUTH 30.49'

SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON DEC. 14, 1999.

TOATL ON ROAD TRAVERSING = 2642.22'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 36" ALLEGAN COUNTY REMONUMENTATION IRON

- NAIL IN W. SIDE 12" ASH N20E 4.95'
- NAIL IN W. SIDE 14" ASH S5E 10.60'
- NAIL IN S. SIDE 8" ASH S80W 5.32'
- NAIL IN S. SIDE 12" TW. CHERRY N20E 14.73'
- M-12, T.1N., R.14W. SOUTH 30.49'

*Raymond Moored* Date 12/24/99

Surveyors License No. 26463

