

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 16 1994
For corners in
ALLEGAN
COMMISSION (County)

1993 DEC 30 PM 2:41
Basil J. Address
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

FILED

	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>13W</u>	<u>E-1 (N 1/4, 6)</u>
	T _____ R _____	<u>TROWBRIDGE TWP.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BASIL ADDRESS, in a field survey on OCTOBER 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
THIS CORNER WAS NOT SET BY THE ORIGINAL GOVERNMENT SURVEYORS.

I COULDN'T LOCATE ANY RECORD OF THIS CORNER EVER BEING ESTABLISHED BY A SURVEYOR.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


SET STD. A. C. MON. ON LINE BETWEEN THE TOWNSHIP COR. AND THE S 1/4 COR. OF SEC-31, ALLEGAN TWP. AND IN LINE WITH OCCUPATION LINE (LG. TREES & OLD FE) TO SOUTH.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 10-26-93.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STD. A. C. MONUMENT (3/4" STEEL PIN & REMON. CAP)
NAIL & REMON. WASHER E SDE TWIN 6" ELMS SOUTH 2.77'
NAIL & REMON WASHER W SDE TWIN 3" OAKS SE 16.63'
NAIL & REMON WASHER S SDE TWIN 8" & 20" W. CHERRY EAST 19.10'
NAIL & REMON WASHER E SDE TWIN 19" & 20" POPLAR NW 166.30'
E & W FENCE SOUTH 2.5' +/-
IN LINE W/ OCCUPATION LINE (LG. TREES & OLD FE) TO SOUTH



Signed by Basil J. Address Date 20 DEC 93
Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1975
REVISED MAY 14, 1975
REVISED JAN., 1983