

SURVEY & REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in ALLEGAN COUNTY

Located In: Corner Code #

- 1. Public Land Survey S1/4 COR SEC. 31 TROWBRIDGE TWP. T.1N R.13W ...B-13....
- 2. Property Controlling in Section S.....T..... R..... S.....T..... R.....
- 3. Miscellaneous Property in Sec. S..... T..... R..... S..... T..... R.....
- 4. Lot No....., Recorded Plat.....
- 5. Private Claims.....

J. E. ...
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.

98 JAN 21 PM 1:36

FILED

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		31		32		33		34		35		36

I, RAYMOND MOORED, in a field survey on SEPT. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-9-97
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PK NAIL PER WIGHTMAN MOORED 1992 SURVEY INFO. IRONS NORTH 33' AND 530' REMAIN.
SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP AND MON. BOX AT FOUND LOCATION.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON 12-9-97

TOTAL ON ROAD TRAVERSING = 5257.27'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP AND MON. BOX.
- NAIL & TAG IN E SIDE P. POLE N2W 75.04'
- NAIL & TAG IN N SIDE 36" MAPLE S80W 194.93'
- SE CORNER POLE BARN (GARAGE) N40W 311.66'
- SW CORNER POLE BARN N65E 200.44'
- C/L ROAD NORTH 4'+/

Raymond Moored Date 12/30/97

Surveyor's Michigan License No. 26463



GOVERNMENT CORNER HISTORY
SOUTH 1/4 CORNER, SECTION 31, TOWN 1 NORTH, RANGE 13 WEST
TROWERIDGE TOWNSHIP

B-13

G.L.O. WM. BROOKFIELD, D.S. 1827
40.00 CHS SET QR. SEC. POST
BEECH 5 N47 1/2 E 14
BEECH 7 N82 W 50

1911 H. MACDOUGAL, COUNTY SURVEYOR
FOUND STONE AT CORNER
MAPLE 14 NORTH 34.5'
HICKORY 10" NW 37'

1992 WIGHTMAN MOORED BOUNDARY SURVEY
SET PK NAIL AT DIST OF 2635.20' FROM SW COR (A-13) PER DISTANCE FROM 1958
SURVEY BY W. Q. SMITH, VAN BUREN CO. SURVEYOR. USED NORTH 1/4 COR,
SEC. 1, BLOOMINGDALE FOR LINE TO EAST FROM A-13. SET IRONS NORTH 33'
AND 530'. C/L ROAD NORTH 4' +/-.

NO OTHER CORNER HISTORY AVAILABLE