

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN

County

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-----------------|
| 1. Public Land Survey | T <u>1N</u> R <u>13W</u> | C-1 (NE, 6) |
| | T _____ R _____ | TROWBRIDGE TWP. |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1993 DEC 30 PM 2:41
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, BASIL ADDRESS in a field survey on OCTOBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O.

- NORTH BETWEEN SECTIONS 5 & 6, T-1N, R-13W
- 76.59 CHS. (5054.94') INTER. N. BOUNDARY SET POST 359 LKS. (236.94')
- WEST OF POST CORNER SECTIONS 5 & 6
- WITNESSES: BEECH 8" S 24 E 16 LKS. (10.56')
- BEECH 11" S 42 W 52 LKS. (34.32')

OLD NOTES (COUNTY SURVEYOR): STAKE & STONE

5-2-90: WIGHTMAN MOORED (RAY E. MOORED) SET 1/2" PIPE AT GOVT. JOG DIST. BY EXTENDING A LINE THRU SE COR SEC-31, T-2N, R-13W FROM N 1/4 COR SEC-5, T-1N, R-13W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FD. 1/2" PIPE PER WIGHTMAN MOORED SURVEY, PIPE FELL 0.41' SOUTH OF TOWNSHIP LINE
- THIS CORNER WAS ESTABLISHED USING IMPROPER PROCEDURES AND IS NOT UTILIZED IN THIS SURVEY.
- SET STD. A. C. MON. ON TOWNSHIP LINE AT GOVT. JOG DIST FROM THE SE COR OF SEC-31, T-2N, R-13W

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 10-26-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STD. A. C. MONUMENT (3/4" STEEL PIN & REMON. CAP)
- NAIL & REMON. WASHER E SDE 7" HACKBERRY SSW 83.96'
- NAIL & REMON. WASHER S SDE 12" ASH NW 15.51'
- NAIL & REMON. WASHER W SDE 22" ASH NNW 13.55'
- NAIL & REMON. WASHER W SDE 9" MAPLE NE 14.16'
- SE COR. SEC-31, T-2N, R-13W (STD. A. C. MON.) EAST 236.94'
- 1/2" PIPE SOUTH 0.41'



Signed by Basil J. Address, Jr. Date 20 Dec 93
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1973
 REVISED JAN., 1983