

**SURVEY &  
REMONUMENTATION**

**APR 07 1998**

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

98 JAN 21 PM 1:36  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
*Joyce A. E. [Signature]*

**FILED**

**SECTION**  
For Corners in  
ALLEGAN COUNTY

Located In: Corner Code #

- 1. Public Land Survey  
SEC COR COMMON  
TO SEC'S 31 & 32  
TROWBRIDGE TWP.      T.1N R.13W      C-13
- 2. Property Controlling  
in Section      S.....T..... R.....
- 3. Miscellaneous  
Property in Sec.      S..... T..... R.....
- 4. Lot No....., Recorded Plat.....
- 5. Private Claims.....

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	20	21	22	23	24	25							
11													
12	31	32	33	34	35	36							
13													

I, RAYMOND MOORED, in a field survey on SEPT. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 12-9-97  
COUNTY REP. K.V.O.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO WM. BROOKFIELD, DS, 1827  
80 CHS SET POST COR SEC'S 31 & 32; BEECH 7 N53 1/4 E 10, BEECH 6 N77W 17  
CONTINUED WEST ON BASELINE 17.15 CHS ( 1131.90' ) TO WEST BNDRY 752 LKS NORTH OF TEMP  
POST AND SET POST COR T1S, R 13 & 14 W.

\*NO OTHER CORNER HISTORY AVAILABLE\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION. ESTABLISHED CORNER POSITION BY PROJECTING LINE FROM B-13 THROUGH NW CORNER, SEC. 6, T1S, R13W AT GLO DISTANCE (1131.90') FROM NW CORNER, SEC. 6. SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP AND MON. BOX AT FOUND LOCATION.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON 12-9-97

TOTAL ON ROAD TRAVERSING = 13,172.41'  
TOTAL OFF ROAD TRAVERSING = 2651.41'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP AND MON. BOX

- NAIL IN SW SIDE P. POLE S30E 70.07'
- NAIL IN NW SIDE P. POLE N45E 88.62'
- TOP C/L TELE. CABLE BOX S5W 38.23'
- NE COR HSE FNDN. S75W 135.13'
- SE COR BRICK GARAGE N60W 146.01'
- CL ROAD 4' +/- SOUTH

*Raymond Moored* Date 12/17/97

Surveyor's Michigan License No. 24463

