

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALLEGAN (County) Located In: Corner Code D-1

1. Public Land Survey T 1N R 13W TROWBRIDGE

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1995 DEC 14 PM 2:39  
 REGISTER OF DEEDS STAMP & FILE NUMBER

**SURVEY & REMONUMENTATION COMMISSION**  
 APR 29 1995

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

DONALD R. PITTS JR. in a field survey on JULY 27, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. 1972 NOT SET BY GOVERNMENT  
 ALLEGAN COUNTY SURVEYOR DONALD A. RATEKIN  
 L.C.R.C. LIBER 1, PAGE 355  
 COULDN'T LOCATE OLD CORNER, SET IRON IN FENCE CORNER INTERSECTION  
 12" MAPLE NORTH 10.8'  
 20" ASH WEST 10.6'  
 16" MAPLE N 70 W 1.3'  
 28" MAPLE S 80 W 5.0'

(CONTINUED ON BACK OF CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2" IRON IN FENCE CORNER INTERSECTION  
 20" ASH WEST 10.6'  
 16" MAPLE N 70 W 1.3'  
 28" MAPLE S 80 W 5.0'  
 PULLED IRON AND SET STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520  
 TRAVERSED 5452' EAST AND 2410' WEST  
 APPROVED BY THE ALLEGAN CO REMON PEER GROUP JUNE 13, 1995, THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 6-13-95  
 COUNTY REP. Donald R. Pitts

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520  
 D-13, T2N, R13W - STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP #23520 EAST 210.69'  
 NAIL & REMON TAG NE SIDE 16" MAPLE N 60°W 2.15'  
 NAIL & REMON TAG N SIDE 36" MAPLE EAST 5.42'  
 NAIL & REMON TAG E SIDE 8" OAK N20°E 24.36'



Signed by Donald R. Pitts Date 30 August 1995  
 Surveyor's Michigan License No. 25867

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

(CONTINUED FROM FRONT OF CERTIFICATE)

- A. 1975 - DONALD A. RATEKIN, COUNTY SURVEYOR  
1/2" IRON  
SAME WITNESSES
- 1977 1/2" IRON  
SAME WITNESSES
- 1983 RAYMOND E. MOORED  
1/2" IRON  
SAME WITNESSES
- 1992 GEORGE MITCHELL  
1/2" IRON  
SAME WITNESSES