

APR 29 1999

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T.....1N R.....13W	D-12
CENTER OF SECTION 32	T..... R.....	.....
TROWBRIDGE TOWNSHIP	T..... R.....	.....
	T..... R.....	.....
2. Property Controlling in section	S.....T.....R.....	.....
	S.....T.....R.....	.....
3. Miscellaneous Property in Sec.	S.....T.....R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

LIBER 007 PAGE 10

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED Nov. 24, 1998  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE PER NUMBER 2 - 5 ON BACK OF SHEET  
CORNER POSITION IS 8.23' SOUTH ON 1/4 LINE FROM TRUE CENTER.

SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.  
THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS.  
THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.  
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON NOV 24, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

-NAIL IN NE SIDE 8" CEDAR	N10°W	21.75'		
-NAIL IN NE SIDE 12" OAK	S10°E	10.12'		
-NAIL IN SE SIDE P POLE	S60°W	43.70'	C-12	N89°57'49"W 2616.94'
-NAIL IN NE SIDE 20" MAPLE	N60°W	64.37'	D-11	N0°25'04"W 2654.08'
-EAST TO C/L M-40		46.3'	D-13	S0°25'04"E 2634.96'
-IN SOUTH WHEEL TRACK OF DRIVEWAY			E-12	S89°49'01"E 2649.03'

Raymond Moored Date 12-1-98

Surveyors License No. 26463



APR 29 1980

SECTION

GOVERNMENT CORNER HISTORY

CENTER OF SECTION 32  
TOWN 1 NORTH, RANGE 13 WEST

D-12

LIBER 007 PAGE 102

1. CORNER NOT SET BY G.L.O.

2. CHICHESTER, COUNTY SURVEYOR, JULY 8th 1864  
AT CENTER OF SECTION 32 ROUNDISH STONE X ON TOP ALSO ON N SIDE,  
SET BY RUNNING BOTH 1/4 LINES

3. DONALD RATEKIN, L.C.R.C. RECORDED LIBER 1, PAGE 207, 04-18-72

FOUND 1" IRON  
SE COR. BARN N 67° W 91.2'  
14" B. ELDER N 43° W 67.95'  
SW COR. BRICK HOUSE EAST 126.5'  
CL M-40 EAST 47'

LIES IN S. WHEEL TRACK OF DRIVEWAY  
RATEKIN USED SAME WITNESSES ON BOUNDARY SURVEY'S DATED  
(05-16-72) (07-12-72) (07-20-73) (04-14-77)

4. DONALD L. BISSELL, L.C.R.C. RECORDED LIBER 003, PAGE 329, 02-23-82

FD. 3/4" PIPE  
S 79° W, 99.0' 36" TRI. ELM  
N 67° W, 91.2', S.E. CORNER OF BARN  
N 43° W, 67.95', 14" BOX ELDER  
EAST, 47.0', E M-40  
LIES IN S. WHEEL TRACK OF DRIVE

5. SECTION CARD INFORMATION:

WIGHTMAN MOORED, INC.  
36" TRI ELM S79°W 99.0'  
SE COR BARN N67°W 91.2'  
14" B. ELDER N43°W 97.95'  
SW COR BRICK HOME EAST 126.5'  
C/L M-40 EAST 47.0'  
LIES IN S. WHEEL TRACK OF DRIVEWAY

HOLLAND ENGINEERING  
FD 3/4" PIPE  
36" TRIPLE ELM S79W 99.00  
SE COR BARN N67W 91.20  
14" BOX ELDER N43W 67.95  
SW COR BRICK HSE E 126.50  
CL M-40 E 47.00

6. M-DOT RIGHT OF WAY MAP

1/4 COR. 47.47'  
W. OF C/L  
1/4 LINE 61.76'  
N. OF P.I.