MOR 2 9 1555

SECTION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

FILED

INFROOD'S PARFIO

FOR CORNERS IN: ALLEGAN COUNTY 1. Public Land Survey	LOCATED IN:	CORNER CODE#	1/28/1999 2:44:39 PN C
S. 1/4 COR COMMON TO SEC. 32 TROWBRIDGE TOWNS 2. Property Controlling	T R SHIP T R T R SR		REGISTER OF DEEDS ALLEGAN COUNTY, NICH C REGISTER OF DEEDS STAMP & FILE NUMBER
in section	sR	***************************************	A B C D E F G H I J K L M
•	SR		2 - 65 - 43 - 21 - 3 4 - 7 - 8 - 9 - 10 - 1112 -
I, Raymond Moored in a fit requirments of P.A. 74, Mi above were in conformanc of survey instructions of the or by a decree of a Court above were in conformance Decree of a Court of Law;	eld survey on Sept. 23, 1998 do hichigan P.A. of 1970, corner points to with regulations and rules there is United States Department of the of Law and/or that the corner points with the rules of the Michigan Brestablished, monumented, recoverners, all the same town and range	ereby state that under mentioned in lines 1 and 2 fore as required in the current of Interior, Bureau of Land mana ts mentioned in the lines 3, 4, a pard of Land Surveyors or by a ered, found as expressed below	agement 11
	a la companya da c	b-compared representations	

A. Description of original monument and accessories and/or subsequent restoration

GLO: -40.00 SET QR. SEC. POST FROM WHICH BEECH 5 N17E 6 BEECH 16 N74W 21

* NO OTHER CORNER HISTORY AVAILABLE *

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY

COUNTY REP.

B.Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION. ESTABLISHED CORNER POSITION BY PROJECTING LINE FROM NORTH 1/4 POST (D-11) THROUGH CENTER (D-12) AND INTERSECTED BASELINE BETWEEN THE SOUTHEAST CORNER AND THE SOUTHWEST CORNER. THE SUUTHEAST CURNER AND THE SUUTHWEST CORNER.
SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP AND MON. BOX AT FOUND LOCATION.
THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON NOV. 24, 1998

TOTAL ON ROAD TRAVERSING = 5253.21'

C.Description of monument for corner and accessories established to perpetuate locating the position of the corner.

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP. -SET NAIL & TAG IN N. SIDE POWER POLE, AZ 86°-34'-40", 73.50' -SET NAIL & TAG IN STOP SIGN, AZ 193°-33'-55", 50.70' -SET NAIL & TAG IN S. SIDE POWER POLE, AZ 224°-55'-45", 115.19' -SET P.K. NAIL IN C/L OF BASELINE ROAD, AZ 91°-03'-45", 9.19'

C-13 589-31-09"W 2607.76"

D-12 NO-25-04"W 2634.96"

E-13 589°-48'-06"E 2645,45"

12/1/98

Surveyors License No. 26463

