

RE...
MAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY
Jasper L. ...

00 FEB -1 AM 8:51

FILED
LIBR0007 PAGE 1, 1

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN: TROWBRIDGE TWP.	CORNER CODE #
1. Public Land Survey	T...1N.. R 13W	...E-3...
SEC. COR COMMON TO SEC'S 4, 5, 8, & 9, TROWBRIDGE TWP.	T..... R.....
	T..... R.....
	T..... R.....
2. Property Controlling in section	S..... T..... R.....
	S..... T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on May 11, 1999, do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3
SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3
FOUND CAPPED IRON IN MON. BOX PER WITNESSES IN #6 & 7 ABOVE. SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 14, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX

- NE COR CONC. HEADWALL N45E 67.60'
- NW COR CONC. HEADWALL N55W 59.15'
- GAS LINE VENT N60W 61.1'
- C/L M-40 HIGHWAY EAST 4.0'
- TELE CABLE MARKER N65E 109.65'
- FD 1/2" IRON W/ WITNESS CORNER CAP S62E 61.40'

Raymond Moored Date 12/13/99

Surveyors License No. 26463



MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY
E-3
TOWN 1 NORTH, RANGE 13 WEST
TROWBRIDGE TOWNSHIP, ALLEGAN COUNTY, MI

1. GLO NOTES SET POST CORNER OF SECTIONS 4,5,8,& 9
 WITNESSES BEECH 22 S 1E 50
 W. OAK 19 N 29W 42
2. IRA CHICHESTER, SURVEYOR
 NOTES RED CEDAR STAKE WITH BLACKSMITH CINDERS
3. COUNTY SURVEYOR NOTES STONE AS CORNER
4. D. ALLEN, CO. SURVEYOR CIRCA 1950'S
 SURVEY FOR W. CARROLL NOTES CORNER; NO WITNESSES
5. D.A. RATEKIN, CO. SURVEYOR
 SECTION CARD NOTES FOR SECTION 4:
 SEC. COR. 4,5,8,& 9 (MSHD)
 BOAT SPIKE OVER STAKE AND STONE
 BM CAP IN ROOT 35 INCH MAPLE S 65°E 74.77 FEET
 CAP IN SIDE OF 19 INCH MAPLE S 47°W 44.52 FEET
 SE CORNER HOUSE FOUNDATION N 44°W 82.53 FEET
6. D.A. RATEKIN, CO. SURVEYOR
 SECTION CARD NOTES FOR SECTION 5:
 SE COR. MON BOX
 NE COR. CONCRETE HDWL N 60°W 50.0 FEET
 SE COR. CONCRETE HDWL S 75°W 46.0 FEET
 GAS LINE VENT N 60°W 61.1 FEET
 C/L HIGHWAY M-40 EAST 3.0 FEET
 SE COR. MON BOX & ROD
 COR. 4 FEET +/- WEST OF C/L CONSTRUCTION
 VENT PIPE CON. POWER CO. NW 61.2 FEET TO C/L
 STEEL FENCE POST NE 75.7 FEET (GEN TELE. CABLE MARKER)
 (WENLEY Q. SMITH JUNE 9, 1974)
7. L.C.R.C. RECORDED BY D.A. RATEKIN 1973
 LIBER 1 PAGE 355 WITNESSES SAME AS ITEM #6
8. D.A. RATEKIN, CO. SURVEYOR
 SURVEY AND SECTION BREAKDOWN FOR DR. W. WELLMAN NOTES CORNER;
 WITNESSES SAME AS ITEM # 8
9. D.A. RATEKIN, CO. SURVEYOR SURVEYS 1973, 1976, 1977
 NOTES CORNER; WITNESSES SAME AS ITEM # 6 & 8 ABOVE
10. WIGHTMAN-MOORED, INC. 1988 THRU 1995, SEVERAL SURVEYS
 NOTES CORNER; NO WITNESSES
11. WIGHTMAN-MOORED, INC. 1990
 SECTION BREAKDOWN INFORMATION NOTES CORNER; NO WITNESSES
12. SHERIDAN SURVEYING CO. 1994
 SECTION BREAKDOWN INFORMATION NOTES E-3 AS CAPPED IRON
13. MOORED LAND SURVEYING 1995
 SURVEY FOR J. WEDGE NOTES CORNER; NO WITNESSES
14. WIGHTMAN-MOORED, INC. 1997
 SURVEY AND SECTION BREAKDOWN FOR JOB #97-045 NOTES CORNER;
 WITNESSES AS FOLLOWS:
 N 35°00'00"W ½ INCH IRON 61.50'
 S 40°00'00"W ½ INCH IRON 53.70'
 N 63°00'00"E ½ INCH IRON 60.80'
 S 62°00'00"E ½ INCH IRON 61.20'
15. MOORED LAND SURVEYING 1998
 SURVEY FOR W. & C. GORBY NOTES CORNER; NO WITNESSES