

**SURVEY
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

SECTION

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

LIBER0007 PAGE 104

FOR CORNERS IN:	LOCATED IN:	CORNER CODE #
ALLEGAN COUNTY		
1. Public Land Survey	T. 1N R. 13W	E-12
1/4 CORNER COMMON TO SECTION 32 & 33 TROWBRIDGE TOWNSHIP	T. R.
	T. R.
	T. R.
2. Property Controlling in section	S. T. R.
	S. T. R.
3. Miscellaneous Property in Sec.	S. T. R.
4. Lot No., Recorded Plat.		
5. Private Claims.		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:**
- G.L.O. 40.00 SET QR SEC POST
W OAK 10 S59E 15
R OAK 30 N24W 12
 - D. RATEKIN, SECTION CARD INFORMATION, COMPUTED LOCATION
DISTANCE FROM E-11 TO E-12 = 2657.38'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 24, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NE CORNER SECTION 32 (E-11) AND EAST 1/8 POST NE 1/4, SECTION 32; 1/8 POST IS IN OCCUPATION N-S AND WEST. COMPUTED LOCATION BY RATEKIN WAS ESTABLISHED BY EXTENDING E-W 1/4 LINE FROM W 1/4 POST EAST THROUGH EXISTING CENTER TO EAST SECTION LINE. THIS POSITION IS 16' +/- SOUTH OF POSITION USING DISTANCE DOUBLED SOUTH FROM EAST 1/8 POST, NE 1/4 AND NE CORNER SECTION 32. HELD POSITION ESTABLISHED BY EAST 1/8 POST AND NE CORNER. SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

E 1/8 POST NE 1/4 = N0°-08'-55" W 1321.58' NE CORNER = N0°-08'-55" W 2643.18'
CENTER = N89°-49'-010" W 2649.03'

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PERR GROUP ON NOV. 24, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
- NAIL & TAG IN W'LY SIDE 20" QUAD MAPLE N20W 13.75'
 - NAIL & TAG IN S'LY SIDE 22" TRIPLE MAPLE N85W 30.65'
 - NAIL & TAG IN W'LY SIDE 15" QUAD MAPLE S10W 26.72'
 - NAIL & TAG IN E'LY SIDE 48" QUAD MAPLE N30E 43.65'
 - IN APPROX. NORTH-SOUTH OCCUPATION LINE

[Signature: Raymond Moored]

Date 12/16/98

Surveyors License No. 76463

