

APR 29 1999

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: ALLEGAN COUNTY
1. Public Land Survey
SEC. COR COMMON TO SEC. 32 & 33 TROWBRIDGE TWP.
2. Property Controlling in section
3. Miscellaneous Property in Sec.
4. Lot No. Recorded Plat.....
5. Private Claims.....

LOCATED IN:
T....1N. R...13W
T..... R.....
T..... R.....
T..... R.....
S.....T.....R.....
S.....T.....R.....
S.....T.....R.....

CORNER CODE #
.....E-13.
.....
.....
.....
.....
.....
.....

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

LIBERO 007 PAGE 1 OF 5

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Aug. 5, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED SEPT. 8, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON PER NUMBER 2 - 4 ON BACK OF SHEET
SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/ CAP IN PLACE OF FOUND CORNER.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

PEER GROUP APPROVED SEPT. 8, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

-NAIL IN NE SIDE 40' TWIN OAK S40°W 68.60'
-NAIL IN NE SIDE P POLE SSW 39.40'
-NAIL IN SW SIDE 16" COTTONWOOD NNE 37.17'
-NAIL IN S SIDE 15" OAK S45°E 72.90'
-C/L OF ROAD NORTH 2.6'

Raymond Moored Date 9/18/98

Surveyors License No. 26463



APR 29 1900

GOVERNMENT CORNER HISTORY

SECTION CORNER COMMON TO SECTIONS 32 & 33
TOWN 1 NORTH, RANGE 13 WEST

SECTION

E-13

1. G.L.O.

80.00 SET POST COR. SECS 32 & 33
BUTTERNUT 10 N 47 1/2 E 29
BUTTERNUT 30 N 39 W 31

2. DONALD RATEKIN, RECORDED SURVEY, LIBER 840 PAGE 114, 05-22-73

FD. IRON		
P.K. NAIL IN 6" ASH	N 15°W	37.7
IRON	NORTH	33'
TELE. POLE	N 58° E	66.2'
POWER POLE	SOUTH	39.7

3. DONALD RATEKIN, RECORDED L.C.R.C., LIBER 2 PAGE 168, 10-30-73

FD. 5/8" IRON ROD		
PK. NAIL IN 6" ASH	N 15°W	37.7
IRON	NORTH	33'
TELE. POLE	N 58° E	66.2'
POWER POLE	SOUTH	39.7

4. SECTION CARDS

WIGHTMAN MOORED, INC.
SW COR SEC 33, 5/8" IRON ROD 6" BELOW RD GRADE

PK NAIL 6" ASH	N15°W	37.7
PROP IRON	NORTH	33'
TELE. POLE	N58°E	66.2'
POWER POLE	SOUTH	39.7

SE COR SEC 32, FND 1" IRON W/CAP

NW COR OF GARAGE	S9°E	37.3'
TELEPHONE POLE	S8°W	39.6'
36" MAPLE	S44°W	68.9'
18" MAPLE	N15°W	37.5'

LIBER 007 PAGE 106