

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

1995 DEC 14 PM 2:39  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 FILED

For corners in  
ALLEGAN (County) Located in: Corner Code #  
 1. Public Land Survey T 1N R 13W E-1  
 T \_\_\_\_\_ R \_\_\_\_\_ TROWBRIDGE  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

**SURVEY &  
 REMONUMENTATION  
 APR 29 1996  
 COMMISSION**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, DONALD R. PITTS, JR., in a field survey on JULY 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. NOT SET BY GOVERNMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 NO PHYSICAL CORNER FOUND  
 SET STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP #23520 ON LINE F-13 TO E-13 T2N, R13W EQUIDISTANT BETWEEN G-1 AND E-1, T1N, R13W.  
 TRAVERSED 2669' EAST AND 5325' WEST  
 APPROVED BY THE ALLEGAN CO. REMON PEER GROUP JUNE 13, 1995, THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS, THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 6-13-95  
 COUNTY REP. Paul J. Van Orden

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 STANDARD ALLEGAN CO. REMON 3/4" X 36" IRON W/RED CAP # 23520  
 NAIL & REMON TAG N SIDE 40" OAK S65°W 22.07'  
 NAIL & REMON TAG NE SIDE TWIN 36" OAK N 60° W 41.05'  
 NAIL & REMON TAG NW SIDE 14" MAPLE N 45° E 44.07'  
 NAIL & REMON TAG S SIDE 14" ASH N 70°E 45.82'



Signed by Donald R. Pitts Jr. Date 30 August 1995  
 Surveyor's Michigan License No. 25867