

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN County	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>13W</u>	<u>G-1</u>
	T _____ R _____	<u>TROWBRIDGE</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:40  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MI  
 FILED

**SURVEY &  
 REMONUMENTATION  
 APR 29 1996  
 COMMISSION**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, DONALD R. PITTS, JR. in a field survey on JULY 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. SET POST @ 78.77, INTERSECTED LINE 115' LKS W OF POST BLUE ASH 9 S 11E 24 W OAK 26 S 53 W 81  
 1983 COUNTY SURVEYORS NOTES  
 SET 1/2" PIPE 3/9/83  
 P.K. S ROOT TWIN (13" & 7") HACKBERRY N 40W 10.20  
 P.K. E SIDE 13" WALNUT N50W 40.83'  
 1/2" PIPE WEST ON SEC LINE 50.00'  
 1/2" PIPE EAST ON SEC LINE 75.90'  
 (SE COR SEC 33 ALLEGAN TWP.)

(CONTINUED ON BACK OF CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON W/CAP "D.E.E. 29245"

- N & T 29245 IN NE OF 14" ELM S 65 E 104.79'  
 N & T 29245 IN NE OF 14" SYCAMORE S 60 E 79.01  
 N & T 29245 IN SE OF 10" ELM S 50 W 31.71'  
 CORNER G-13, ALLEGAN TWP. S 85 E 75.90'  
 CAPPED IRON # 26463 S 08 W 19.82'  
 CAPPED IRON # 26463 M 61 E 90.00'


APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 6-13-95  
 COUNTY REP. Donald R. Pitts, Jr.

PULLED IRON, SET STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP #23520 ON LINE G-13 TO F-13, T2N, R13W 75.85' W OF G-13  
 TRAVERSED 76' EAST AND 7994 WEST  
 APPROVED BY ALLEGAN CO. REMON PEER GROUP JUNE 13, 1995, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520  
 G-13, T2N, R13W - STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520 EAST 75.85'  
 N & T #29245 SE SIDE 10" ELM S 50 W 31.15'  
 N & T NE SIDE 14" SYCAMORE S 60 E 78.67'  
 NAILS & REMON TAG NE SIDE 12" OAK N 30 W 40.76'

Signed by Donald R. Pitts, Jr. Date 30 August 1995  
 Surveyor's Michigan License No. 25867



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

CONTINUED FROM FRONT OF CERTIFICATE

A. 1994 DAVID E. ERICKSON  
L.C.R.C. LIBER 4, PAGE 391  
SET 1/2" IRON W/CAP "DEE 29245"  
SET N & T 29245 IN NE OF 14" ELM S 65 E 104.79'  
SET N & T 29245 IN NE OF 14" SYCAMORE S 60 E 79.01'  
SET N & T 29245 IN SE OF 10" ELM S 50 W 31.71'  
CORNER G-13, ALLEGAN TWP. S 85 E 75.90'  
FOUND CAPPED IRON # 26463 S08 W 19.82'  
FOUND CAPPED IRON # 26463 N 61 E 90.00'