

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN  
(County)

Located In:

Corner Code G-2

1. Public Land Survey

T 1N R 13W

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling  
in Section

S \_\_\_\_\_

T \_\_\_\_\_

R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_

T \_\_\_\_\_

R \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_

R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1995 DEC 14 PM 2:40  
Register of Deeds Stamp & File Number  
FILED

SURVEY &  
REMONUMENTATION

APR 29 1996

COMMISSION

I, DONALD R. PITTS, JR. in a field survey on SEPTEMBER 19, 1995  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessions and/or subsequent restoration:

- G.L.O. - SET POST  
BUTTERNUT 8 S13E 17  
LYNN 8 N70E 8
- CIRCA 1900 - COUNTY SURVEYORS NOTES  
S & S  
ELM ? ?  
ELM ? 10'
- 1983 - RAYMOND E. MOORED  
SET 1/2" x 3" PIPE W/CAP

(CONTINUED ON BACK OF CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- FOUND 1/2" x 5' REBAR W/CAP "D.E.E. 29245"
- S72W 62.66' 1/2" REBAR ON WEST SIDE OF CREEK, COURSE NW
- N90W 59.22' CAPPED PIPE # 26463 IN CL CREEK, COURSE NW
- S18E 14.71' N&T 29245 IN W OF 8" ASH
- N74E 17.78' 1/2" REBAR
- SOUTH 50' NE'LY BANK OF STREAM
- PULLED REBAR AND SET 1/2" x 5' PIPE W/ALLEGAN CO. REMON. RED CAP #23520
- TRAVERSED 2548' NORTH AND 2635' SOUTH

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 6-13-95  
COUNTY REP. Richard Van Orden

APPROVED BY THE ALLEGAN CO. REMON PEER GROUP JUNE 13, 1995, AND IS ACCEPTED AS A CAREFUL  
AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" x 5' PIPE W/ALLEGAN CO. REMON CAP # 23520
- 1/2" REBAR ON WEST SIDE OF CREEK, COURSE NW S72W 62.66'
- CAPPED PIPE # 26463 IN CL CREEK, COURSE NW N90W 59.22'
- N&T 29245 IN W SIDE OF 8" ASH S18E 14.71'
- 1/2" REBAR N74E 17.78'
- NE'LY BANK OF STREAM SOUTH 50'



Signed by Donald R. Pitts, Jr. Date 22 September 1995

Surveyor's Michigan License No. 25867

0005 PAGE 304

PAGE 1 OF 2

## CONTINUED FROM FRONT OF CERTIFICATE

## A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION.

CENTERLINE 8' CREEK E 1'±  
 1/2" PIPE W/CAP WEST 350.28 (P.O.T.)  
 TOP OF BANK WEST 330'±  
 6" STEEL FENCE POST S 0.3'±  
 (PAINTED RED)

1994 - DAVID E. ERICKSON

L.C.R.C. LIBER 4, PAGE 390

SET 1/2" x 5' REBAR WITH CAP "DEE 29245"	
S72W 62.66'	SET 1/2" REBAR ON WEST SIDE OF CREEK, COURSE NW
N90W 59.22'	CAPPED PIPE # 26463 IN CL CREEK, COURSE NW
S18E 14.71'	SET N&T 29245 IN W OF 8" ASH
N74E 17.78'	SET 1/2" REBAR
SOUTH 50'	NE'LY BANK OF STREAM