

SURVEY & REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>1N</u> R <u>13W</u>	<u>G-6</u>
	T _____ R _____	<u>W 1/4 Cor.</u>
	T _____ R _____	<u>Sec. 15</u>
	T _____ R _____	<u>E 1/4 Cor.</u>
2. Property Controlling in Section	S _____ T _____ R _____	<u>Sec. 16</u>
	S _____ T _____ R _____	<u>Trowbridge</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>Twp.</u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 30 PM 12:18
 Register of Deeds
 ALLEGAN COUNTY MICHIGAN
Joyce A. Batten

FILED

Register of Deeds Stamp & File Number

I, Kirk Van Order, in a field survey on May 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-6
- GLO set post at 40.00 chains North of G-7.
 - 7" Beech S47°W 13 links
 - 26" Beech N71°E 26 links
 - Old survey, undated and unsigned, shows stone at corner.
 - No recorded LCRC

(Continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-6
- Fd. 1" x 60" pipe using Van Order tie info.
Also corner of recorded plat "Belden Sub."

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group approved 6-14-94.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 6-14-94
 COUNTY REP. Kirk Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-6
- Replaced pipe with a standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
- | | | |
|--|------|--------|
| Nail & Remon. tag in N side 46" Ash | W,NW | 52.64' |
| Nail & Remon. tag in NE side 22" Ash | NW | 7.52' |
| Nail & Remon. tag in NW side 7" Basswood | NE | 32.82' |
| Nail & Remon. tag in 24" Basswood | E,NE | 6.96' |
| Nail in E side RR Tie End Fence Post | S | 1.05' |

Signed by *Kirk Van Order* Date 12-30-94
 Surveyor's Michigan License No. 23520

REF: 0005 PAGE 156

Page 1 of 2

Section A (continued from Page 1)G-6

•Ratekin witness card shows no ties at corner

•K.V.O. survey (93-2974) 8-18-1993

Fd. 1" Pipe w/2 small stones on N side

Nail in N side 24" Basswood	E,NE	6.92'
Nail in E side Wood Fence Post	S,SE	1.04'
Nail in NE side 22" Ash	NW	7.54'
Nail in NW side 6" Basswood	NE	32.85'

Page Wire Fence to South