

**SURVEY
REMONUMENTATION**

APR 29 1998

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBERO 007 PAGE 107

For corners in

<u>ALLEGAN</u>	Located In:	Corner Code #
(County)	TROWBRIDGE TWP.	
1. Public Land Survey	<u>T 1 N R 13 W</u>	<u>G-8</u>
QUARTER CORNER	T ___ R ___	_____
COMMON TO SECTIONS	T ___ R ___	_____
21&22	T ___ R ___	_____
2. Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims _____		

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

I, **BERYL M. JONES** in a field survey on February 24, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 GLO - North Between Sections 21 and 22 1900 - County Surveyor notes - County surveyor notes
 40.00 Set Post Gray Sand Stone, Broken West 1/4 Post - R. Tie (stone Was Removed
 Beech 10 N38E 11 on 2 Sides X on N. Side by Farmer - To Be Replaced)
 Sugar 10 N74W 42 Oak N. 4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Gray Stone Broken on Two sides "X" on North Side.
 R.R. tie W/Old Fence N.0W. 0.5' N..
 Found Capped Iron W/Cap #26463 N5E 10.85' of Stone.
 Center of 54" Oak Stump 4.5' North of Iron
 No History

 Accepted Stone. Removed Stone and Pulled Iron.
 Set Standard Allegan Co. Remon. 3/4" x 36" Iron W/Red Cap #23520.
 Approved by the Allegan Co. Remon. Peer group on October 10, 1995

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED OCT. 10, 1995
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Standard Allegan Co. remon. 3/4" x 36" Iron W/Red Cap #23520
 NAIL W/ REMON. TAG AND WASHER S. SIDE 16" MAPLE W 24.16'
 NAIL W/ REMON. TAG AND WASHER W SIDE 8" OAK S.,SE 19.87'
 NAIL W/ REMON. TAG AND WASHER S SIDE 14" HICKORY E 39.00'
 NAIL W/ REMON. TAG AND WASHER SE SIDE 20" W. OAK NE 46.50'
 RR TIE CORNER POST N .50' +/-



Signed by [Signature] Date 4/9/98 April 9, 1998
 Surveyor's Michigan License No. #23514