

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located in:	Corner Code #
1. Public Land Survey	T 1N R 13W	G-9
	T _____ R _____	TROWBRIDGE
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

1995 DEC 14 PM 2:40
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

SURVEY &
 REMONUMENTATION
 APR 29 1995
 COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DONALD R. PITTS, JR., in a field survey on SEPTEMBER 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. NORTH BETWEEN SECTIONS 27 AND 28 80.00 SET POST CORNER SECTIONS 21, 22, 27 AND 28
 BEECH 8 N 36W 23
 BEECH 17 S 80 E 12

CIRCA 1900 COUNTY SURVEYOR NOTES
 SMALL ROUND GREY SAND STONE WITH HALF OF A BRICK UNDER STONE
 HICKORY 10" SW 35.5'
 OAK 24" SE 81'
 ST. SIGN NE 27.6'
 B.M. SW 59.4'

(CONTINUED ON BACK OF CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 5/8" IRON IN MON BOX
 NAIL IN W SIDE 68" B. OAK SSE 81.43'
 NAIL IN NW SIDE 15" TW HICKORY SW 35.69'
 SW CORNER METAL BLDG FNDN NE 54.64'
 CL TELE PEDESTAL N 30.11'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 9-12-95
 COUNTY REP. Donald R. Pitts, Jr.

PULLED IRON AND SET STANDARD ALLEGAN CO. REMON 3/4" x 24" IRON W/RED CAP # 23520 IN MON BOX. APPROVED BY ALLEGAN CO. REMON PEER GROUP ON SEPTEMBER 12, 1995 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD ALLEGAN CO. REMON 3/4" x 24" IRON W/RED CAP #23520 IN MON BOX.
 NAIL & REMON TAG W SIDE 68" BLACK OAK S 15° E 81.43'
 NAIL & REMON TAG NW SIDE 15" TWIN HICKORY S 40° W 35.69'
 SW CORNER METAL BLDG FNDN N 40° E 54.64'
 CL TELEPHONE PEDESTAL NORTH 30.11'



Signed by Donald R. Pitts, Jr. Date 22 September 1995
 Surveyor's Michigan License No. 25867

(CONTINUED FROM FRONT OF CERTIFICATE)

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION

- 1972 DONALD A. RATEKIN, COUNTY SURVEYOR
L.C.R.C. LIBER 2, PAGE 25
FOUND 5/8" IRON
68" OAK S 10° E 79.3'
14" TWIN HICKORY S 35°W 35'
16" HICKORY N 80° E 133.1'
ST SIGN N 55° E 45.6'
FENCE POST N 26.7'
- 1976 DONALD A. RATEKIN, COUNTY SURVEYOR
UNRECORDED SURVEY
5/8" IRON
SAME WITNESSES AS L.E.R.C. LIBER 2, PAGE 25
- 1992 KIRK L. VAN ORDER, COUNTY SURVEYOR
UNRECORDED SURVEY
FOUND 1" IRON
SET NAIL IN W SIDE 68" B. OAK S.S.E 81.43'
SET NAIL IN NW SIDE 15" TW HICKORY SW 35.69'
SW CORNER METAL BLDG FNDN NE 54.64'
CL TELE PEDESTAL N 30.11"