

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>R13W</u>	<u>H-1</u>
	T _____ R _____	<u>TROWBRIDGE</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:40
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICH.
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

**SURVEY &
 REMONUMENTATION**

APR 29 1996

COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

DONALD R. PITTS, JR. in a field survey on JULY 27, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


G.L.C. NOT SET BY GOVERNMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO PHYSICAL CORNER FOUND
 SET STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520, ON LINE H-13 AND G-13, T2N, R13W EQUIDISTANT BETWEEN G-1 AND I-1, T1N, R13W.
 TRAVERSED 2636' WEST AND 2707' EAST
 APPROVED BY THE ALLEGAN CO. REMON PEER GROUP JUNE 13, 1995
 THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 6-13-95
 COUNTY REP. Donald R. Pitts, Jr.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520
 H-13, T2N, R13W STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/CAP #23520 ESAT 68.85'
 NAIL & REMON TAG W SIDE 18" OAK S 10DEG W 42.33'
 NAIL & REMON TAG E SIDE 8" OAK S 60DEG W 58.64'
 NAIL & REMON TAG E SIDE 14" OAK S 35DEG E 62.25'



Signed by Donald R. Pitts, Jr. Date 23 August 1995
 Surveyor's Michigan License No. 25867

0005 PAGE 308