

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>13W</u>	<u>I-1</u>
	T _____ R _____	<u>TROWBRIDGE</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:40
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

**SURVEY &
 REMONUMENTATION
 COMMISSION**

APR 29 1996

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

DONALD R. PITTS JR. in a field survey on JULY 27, 1995
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as
 expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O.-SET POST @ 79.59 - 109 LKS WEST OF POST
 W. OAK 15 S7E 55
 W. OAK 17 S32W 92
 CIRCA-1900 - COUNTY SURVEYORS NOTES
 STONE
 HICKORY S.W. 75'
 HICKORY EAST 17'
 HICKORY SSE 33'
 JOG 109 lks W


(CONTINUED ON BACK OF CERTIFICATE)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON
 P.K. N SIDE 24" OAK WEST 44.75'
 P.K. S SIDE 24" HICKORY N 85E 18.60'
 P.K. E SIDE 18" HICKORY S30W 74.75'
 CL 28th ST EAST 2'±
 FOUND I-13, T2N, R13W 70.66' EAST
 PULLED IRON AND SET STANDARD ALLEGAN CO. REMON. 3/4" x 24" IRON W/RED CAP #23520 ON TOWN LINE
 70.66' WEST OF I-13 T2N, R13W
 TRAVERSED 5196' WEST AND 71' EAST
 APPROVED BY THE ALLEGAN CO. REMON PEER GROUP JUNE 13, 1995 AND IS ACCEPTED AS A CAREFUL AND
 FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 6-13-95
 COUNTY REP. Donald R. Pitts Jr.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 STANDARD ALLEGAN CO. REMON 3/4" x 24" IRON W/RED CAP # 23520
 I-13 T2N, R13 W STANDARD ALLEGAN COUNTY REMON 3/4" x 36" IRON W/RED CAP #23520 EAST 70.66'
 NAIL & REMON TAG N. SIDE 36" OAK WEST 44.75'
 NAIL & REMON TAG S. SIDE 24" HICKORY EAST 18.32'
 NAIL & REMON TAG E. SIDE 20" HICKORY S 15DEG WEST 75.64'
 CENTERLINE 28th ST EAST 2'±



Signed by Donald R. Pitts Jr.
 Surveyor's Michigan License No. 25867

Date 29 August 1995

0005 PAGE 309

SHEET 1 OF 2

(CONTINUED FROM FRONT OF CERTIFICATE)

A. 1969-COUNTY SURVEYORS NOTES

STONE (IRON OVER)
S.E. COR SEC 34 IRON E. 70.78'
20" HICKORY E 17.3'
19" HICKORY SSW 73.95'
21" B OAK W 43.7'

1981-COUNTY SURVEYORS NOTES

FOUND 3/4" IRON
P.K. N SIDE 24" OAK WEST 44.75'
P.K. S SIDE 24" HICKORY N85E 18.60'
P.K. E SIDE 18" HICKORY S30W 74.75'
P.K. SW SIDE 12 " W CHERRY N 30 W 55.17'
CL 28th ST EAST 2'±