

**ALLEGAN CO. REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALLEGAN (County) Located in \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T-1N R-13W K-13, SW 36  
TROWBRIDGE

2. Property Controlling in Section \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

97 JAN 22 PM 1:28  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY  
 FILED  
 Register of Deeds Stamp & File Number

I, BASIL ADDRESS, in a field survey on MAY 18, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. 1977 D.A. RATEKIN, C.S.  
 80.00 SET POST COR SECS 35 & 36 WITNESS CARD  
 MAPLE 9 N 4 1/2 E 32' 1/2" IRON  
 MAPLE 12 N 84 1/2 W 57' IN C.L. E-W RD, C.L. RD N - 5' E  
 T.P. N 20° E 68.04  
 4" - 10" HICKORY S 55° W 28.55'  
 9" ELM S 50° E 30.01'  
 W. EDGE W. LEG SIGN S 05° E 13.33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Rd 1/2" IRON W/ CAP (REM 26463)  
 14" HICKORY S 55° W 28.5'  
 IN C.L. E-W RD, C.L. RD N - 5' E  
 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 REPLACED 1/2" IRON W/ STD. ALLEGAN CO. MON.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 5-14-96  
 COUNTY REP. Basil J. Address

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 ALLEGAN CO. MONUMENT  
 16d & ALLEGAN CO. TAG NW SDE 14" HICKORY S 55° W 28.46'  
 16d & ALLEGAN CO. TAG S'LY SDE 10"-12"-16" ASH N 75° W 94.34'  
 16d & ALLEGAN CO. TAG SE SDE COR. FE POST N 40° E 52.20'  
 E. EDGE STOP SIGN POST N 10° W 44.74'  
 E. EDGE WEST SIGN POST S'LY 14.85'  
 S.E. COR TEL PED. N 25° E 69.28'  
 IN C.L. BASELINE RD  
 C.L. 26TH ST TO NORTH IS EAST 5'±



Signed by Basil J. Address Date 10 JUN 96  
 Surveyor's Michigan License No. 30075