

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS  
ALLEGAN COUNTY, MI  
*James A. ...*

00 FEB - 1 AM 8:51

FILED

LIBRARY / FILE 445

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T...1.N R...13W	M-9
NE CORNER, SEC. 25, TROWBRIDGE TWP.	T..... R.....	.....
	T..... R.....	.....
	T..... R.....	.....
2. Property Controlling in section	S.....T.....R.....	.....
	S.....T.....R.....	.....
3. Miscellaneous Property in Sec.	S.....T.....R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC. 14, 1999  
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON IN MONUMENT BOX PER NUMBERS 2,5,7, AND 8 LISTED ON BACK OF SHEET.  
SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER.  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 14, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.
- NAIL & TAG IN 18" MAPLE N 35°E 67.20'
- C/L ASPHALT PAVEMENT NORTH 15.00'
- NAIL & TAG IN 30" MAPLE S 35°E 53.70'
- TOP C/L TELEPHONE BOX S 45°W 49.20'
- NAIL & TAG IN 12" TWIN MULBERRY N 45°W 81.50'
- A-9, T1N, R12W NORTH 29.04'

*Raymond Moored* Date 12/24/99  
Surveyors License No. 26463



MAR 07 2000

SECTION

LIBR0007 PAGES 1-6

**GOVERNMENT CORNER HISTORY FOR  
M-9  
TOWN 1 NORTH, RANGE 13 WEST,  
TROWBRIDGE TOWNSHIP, ALLEGAN COUNTY, MICHIGAN**

1. Wm. BROOKFIELD, DEPUTY SURVEYOR 1827  
SET CORNER POST  
WITS: BEECH 10 S 13W 43  
BEECH 10 N 16 W 68
  
2. D.A. RATEKIN, CO. SURVEYOR  
SECTION CARD INFORMATION SECTION 24  
NOTES 1 INCH IRON  
29.04' S OF SW COR. SEC. 19 OTSEGO TWP.  
12" MAPLE N 35°E 67.4'  
C/L ASPHALT PVMT N 16'  
30" MAPLE S 35°E 53.7'  
ST. SIGN S 70°W 38.8'
  
3. D.A. RATEKIN, CO. SURVEYOR  
SECTION CARD INFORMATION SECTION 25  
NOTES: 12" MAPLE N 35°E 65.4' (BLAZE)  
OTHER WITS SAME AS ITEM # 2  
FD. 1985 ¾" IRON (A.K.A. 1" IRON)
  
4. D.A. RATEKIN, CO. SURVEYOR  
SECTION BREAKDOWN NO CORNER, NO WITS.
  
5. D.A. RATEKIN, CO. SURVEYOR 1969  
SURVEY NOTES CORNER. NO WITS.
  
6. L.C.R.C. RECORDED BY D.A. RATEKIN 1971  
WITNESSES SAME AS ITEM # 3
  
7. D.A. RATEKIN, CO. SURVEYOR 1972  
SURVEY FOR R. HOWRIGON NOTES CORNER AND WITS SAME AS ITEM #3
  
8. D.A. RATEKIN, CO. SURVEYOR 1978  
NOTES CORNER, NO WITS.
  
9. TRI-COUNTY LAND SURVEYS, INC. 1985  
SURVEY FOR M. BUCK NOTES CORNER, NO WITS.
  
10. K. VAN ORDER, CO. SURVEYOR 1989  
SECTION BREAKDOWN NOTES CORNER AND WITS SAME AS ITEM #2  
NEW WITS AS FOLLOWS

