

RE

MAR 17 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*Joyce A. [Signature]*

00 FEB - 1 AM 8:51

FILED  
LIBR0007 P006457

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN: TROWBRIDGE TWP.	CORNER CODE #
1. Public Land Survey	T...1N... R...13W	M-10
E. 1/4 CORNER SECTION 25, TROWBRIDGE	T..... R.....	.....
	T..... R.....	.....
	T..... R.....	.....
2. Property Controlling in section	S.....T.....R.....	.....
	S.....T.....R.....	.....
3. Miscellaneous Property in Sec.	S.....T.....R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Aug. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
SEE BACK OF SHEET FOR GOVERNMENT CORNER HISTORY

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC. 14, 1999  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" STEEL ROD PER NUMBER 4 LISTED ON BACK OF SHEET  
SET 3/4" X 24" ALLEGAN COUNTY REMON W/CAP IN PLACE OF FOUND CORNER.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 14, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP

- NW CORNER HOUSE FOUNDATION S40E 59.50'
- NE CORNER HOUSE FOUNDATION S50W 110.15'
- NW CORNER METAL BUILDING S20W 132.70'
- NE CORNER METAL BUILDING S25E 127.28'
- NAIL & TAG IN 44" CHERRY N50W 51.82'

Raymond Moored Date 12/24/99

Surveyors License No. 26463

PAGE 1 of 2



MAR 07 2006

SECTION

**M-10**

**EAST 1/4 CORNER  
TOWN 1 NORTH, RANGE 13 WEST  
TROWBRIDGE TOWNSHIP**

**A. Description of original monument and accessories and/or subsequent restoration:**

**1. GLO**

40.00 Set qr. Sec. post  
Beech 15 S31W 12  
Beech 7 N42W 26

**2. Donald A. Ratekin, Section card information, 8-26-69  
Found 1" Iron**

**3. Wightman-Moored, Inc., Unrecorded Boundary Survey, Dated: 11-13-95  
Distance Between M-9 and M-10 = S00°34'06"W 2651.61'**

**4. Kirk VanOrder, County Surveyor, Field Notes, Job #89-1894 Dated: 1989  
Distance Between M-10 and M-11 = N00°05'12"W 2642.47'**

Fd. 1 1/4" Steel Rod  
-NW Cor. Barn Fnd. SE 59.50'  
-NE Cor. Hse. Fnd. SW 110.15'  
-44" Cherry NW 51.82'  
-NW Cor. Metal Bldg. S,SW 132.70'  
-NE Cor. Metal Bldg. S,SE 127.28'

**5. Kirk VanOrder, County Surveyor, Unrecorded Boundary Survey Dated: 4-4-89  
Shows Same information as # 4 from above.**

**6. Donald A. Ratekin Section Breakdown Notes  
Distance Between M-9 and M-10 = 2638.693 S0°05'00"E  
Distance Between M-10 and M-11 = 2642.425 S0°05'03"E  
Distance Between M-10 and L-10 = 2631.912**

**7. Kirk VanOrder, County Surveyor Section Card**

1" Iron  
-30" Cherry NW 51.2'  
-NE Cor. Hse. SW 109.9'  
-NW Cor. Barn Fnd. SW 59.5'

Also shows same information as # 4 and # 6 from above.



LIBRARY / MAR 14 2006