

**ALLEGAN CO. REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>ALLEGAN</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T-1N R-13W	M-12, E 1/2 36
	T _____ R _____	TROWBRIDGE
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

97 JUN 22 PM 1:28
REGISTERED
ALLEGAN COUNTY
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	20	25	28	27	26	25						
11												
12	31	32	33	34	35	36	X					
13												

I, BASIL ANDRESS, in a field survey on MAY 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. 1977 D.A. RATEKIN, C.S.
 SET QR. SEC. POST WITNESS CARD
 CHERRY 7 N 69° W 13 1/2" IRON
 SUGAR 8 S 20° W 33 C.L. RD EAST 3'
 IN LINE W/ FE TO WEST
 CUT NAIL S. SDE PP EAST 57.94'
 CUT NAIL SW SDE T.P. N 20° W 104.83'
 P.K. NE SDE 3" - 4" ELM N 65° W 58.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Fd 1/2" IRON
 C.L. RD EAST 3'±
 IN LINE W/ FE TO WEST
 CUT NAIL S. SDE P.P. EAST 58.00'
 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 REPLACED 1/2" IRON W/ STD. ALLEGAN CO. MON.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 5-14-96
 COUNTY REP. Basil J. Andress

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ALLEGAN CO. MONUMENT
 CUT "X" N. END 12" STEEL CULV. N 30° E 46.78'
 CUT NAIL S. SDE P.P. S 85° E 58.00'
 16d & ALLEGAN CO. TAG W. SDE 6" BLACK TUPELO N 20° W 116.25'
 16d & ALLEGAN CO. TAG S. SDE COR. FE POST WEST 26.82'
 M-11 N 00°-00'-00" E 2640.52'
 M-13 S 00°-00'-00" W 2634.13'
 C.L. 24TH ST EAST 3'±
 IN LINE W/ FE TO WEST



Signed by Basil J. Andress Date 10 JUN 96
 Surveyor's Michigan License No. 30075

USE 0605 PAGE 510