

MAR 07 2000

FILED

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

00 FEB -1 AM 8:36

LIBERO 007 PAGE 166

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN: CHESHIRE TOWNSHIP	CORNER CODE #
1. Public Land Survey	T...1N. R...14W	.....A-11
SOUTHWEST SEC. 30	T..... R.....	.....
NORTHWEST SEC.31	T..... R.....	.....
CHESHIRE TOWNSHIP	T..... R.....	.....
2. Property Controlling in section	S.....T.....R.....	.....
	S.....T.....R.....	.....
3. Miscellaneous Property in Sec.	S.....T.....R.....	.....
4. Lot No.....,Recorded Plat.....		
5. Private Claims.....		

*Jayce L. Little*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Aug 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR GOVERNMENT CORNER HISTORY

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED OCT. 12, 1999  
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1/2" IRON ROD ON TOWN LINE AT GOVERNMENT JOG DISTANCE (107.58") SOUTH OF LEE TOWNSHIP CORNER  
REMOVED 1/2" IRON AND SET ALLEGAN COUNTY REMON IRON WITH CAP  
TOTAL ON ROAD TRAVERSING = 2651'  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- POWER POLE NORTH 138.50'
- CENTER OF ROAD NORTH 42.70'
- N.W. COR. ELEC. BOX S80°E 59.8'
- NAIL S. SIDE P.P. 18" ABOVE GROUND S70°E 52.6'
- NE COR. SEC. 36, T.1N., R.15W. NORTH 107.58'

*Raymond Moored*  
Surveyors Liscense No. 26463

Date 12/15/99



MAR 07 2000

SECTION

A-11

**SOUTHWEST CORNER SECTION 30  
NORTHWEST CORNER SECTION 31  
TOWN 1 NORTH, RANGE 14 WEST**

11000007 PAGE 167

A. Description of original monument and accessories and/or subsequent restoration:

1. GLO

Set post cor. Secs 30 & 31  
Sugar 14 N36E 29  
Beech 14 S48E 92

2. County Surveyor notes, circa 1800's

Set Stone for Section Corner  
A-11 South to A-13 = 5210.5  
A-11 North to A-10 = 2635  
A-11 East to B-11 = 2681 ½  
1 ¼" Pipe in W. Track  
PP SE 146.5  
St. sign NNE 66.4  
107.58 South of NE Cor. Sec. 36 Lee

3. E. Strong, Deputy County Surveyor, Aug. 23, 1871

Notes for Section 31, Survey  
A-11 South to A-12 = 39.46 (2604.36')  
A-11 South to A-13 = 78.92 ½ (5209.05') Var. 3°12'  
A-11 East to B-11 = 40.73 (2688.18')  
A-11 East to C-11 = 80.69 (5325.54') Var. 3°48'

4. Hugh MacDougal, County Surveyor, Circa 1900's

Description of Brush Creek Drain  
Quote "At a point 22.42 rods North and 40 rods East of the SW Cor. of Sec. 30"

5. Don Allen, County Surveyor, June 8, 1961

Unrecorded Boundary Survey  
Noted Iron (no witnesses)  
A-11 North to C/L of 102<sup>nd</sup> Ave. = 54'  
A-11 North to Creek = 278'

6. Donald Ratekin, County Surveyor, Circa 1980

Field Notes from Job #80-6029  
M-11 (Lee Twp.) South to A-11 (Cheshire Twp.) = 107.58'  
A-11 East to B-11 = N 89°44'02" E 2682.48'  
A-12 North to A-11 = N 0°19'43" E 2543.02'

7. Wightman-Moored Inc., 4-26-1988

Notes for Unrecorded Boundary Survey located in the NW ¼, Section 31  
A-11 East to B-11 = N 89°44'02" E 2682.48'  
A-12 NORTH TO A-11 = N 0°19'43" E 2543.02'