

MAR 07 2000

FILED

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

00 FEB -1 AM 8:36

FOR CORNERS IN: ALLEGAN COUNTY
 1. Public Land Survey LOCATED IN: T...1N. R14W... CORNER CODE # A-12.....
 T..... R..... CHESHIRE TWP.
 WEST 1/4 POST of SECTION 31, T1N, R14W
 T..... R.....
 T..... R.....
 2. Property Controlling in section S.....T.....R.....
 S.....T.....R.....
 3. Miscellaneous Property in Sec. S.....T.....R.....
 4. Lot No....., Recorded Plat.....
 5. Private Claims.....

Jayne L. Stettin
REGISTER OF DEEDS
ALLEGAN COUNTY, MI.

REGISTER OF DEEDS STAMP & FILE NUMBER

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED OCT. 12, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON ROD ON TOWNSHIP LINE PER NUMBER 3 AND 4 ON BACK OF THIS SHEET.
REMOVED FOUND CORNER AND SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP.
THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999.

TOTAL ON ROAD TRAVERSING = 2651.70'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

- ELECTRIC BOX N85W 27.50'
- NAIL & TAG IN 18" SYCAMORE N50W 93.60'
- NAIL & TAG IN 18" OAK S45W 44.30'
- NAIL & TAG IN 6" SYCAMORE S40E 48.70'
- C/L ROAD TO WEST NORTH 45' +/-
- M-12, T.1N., R.15W. NORTH 53.79'

Raymond Moored Date 12/15/99
Surveyors License No. 26463



LIBRARY 007 PART 168

MAR 07 2000

SECTION

A-12

WEST 1/4 POST OF SECTION 31
TOWN 1 NORTH, RANGE 14 WEST,

A. Description of original monument and accessories and/or subsequent restoration:

1. GLO-This corner not set by G.L.O.

2. County Surveyor notes, circa 1900's

| | |
|---------------------|------------------|
| A-12 north to A-11= | 39.46 (2604.36') |
| A-12 south to A-13= | 39.46 (2604.36') |
| A-12 east to B-12= | 40.22 (2654.52') |

3. DA Ratekin & Associates, circa 1980

Field notes for section 31, Job #80-6029

| | | |
|---------------------|-----------------|---------|
| A-12 North to A-11= | N 0°-19'-43" E | 2543.02 |
| A-13 North to A-12= | N 0°-19'-15" E | 2650.61 |
| B-12 West to A-12= | N 89°-51'-14" W | 2658.35 |

Jog between A-12 Cheshire Township and M-12 Lee Township = 53.79'

4. DA Ratekin, Section Card Information

West 1/4 post 1" iron 3-21-80

East 1/4 post Sec. 36, Lee Township, North 53.79'

| | | |
|-------------------------|-------|--------|
| PK NE side 14" Ash | N55°W | 94.40' |
| PK N side 12" Cherry | N85°W | 24.30' |
| PK SW side 30" Sycamore | S70°E | 67.09' |
| C/L St. sign | N20°E | 34.8' |

Jog between A-12 Cheshire Township and M-12 Lee Township = 53.79'



RECORDED / MAR 10 2000