

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

97 JUN 22 PM 1:14  
 FILED  
 REGISTERED  
 ALLEGAN COUNTY

For Corners in ALLEGAN COUNTY Located In: Corner Code #

1. Public Land Survey T..1N R..14W \* A-13 CHESHIRE TWP.  
 SOUTHWEST 1/4 COR. T..1N... R..15W M-13 LEE TWP.  
 SEC. 31, T1N, R14W T..... R.....  
 SEC. 36, T1N, R15W T..... R.....
2. Property Controlling S.....T..... R.....  
 in Section S.....T..... R.....
3. Miscellaneous S..... T..... R.....  
 Property in Sec. S..... T..... R.....
4. Lot No....., Recorded Plat.....  
 5. Private Claims.....

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RAYMOND MOORED, in a field survey on OCT, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 1" IRON PER ACCESSORIES ABOVE. REPLACED WITH STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON & CAP, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 10-3-96.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY

DATE APPROVED 10-8-96  
 COUNTY REP. *Raymond E. Moored*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- NAIL & TAG IN E. SIDE 12" ELM N45°W 25.29'
  - NAIL & TAG IN W. SIDE 48" MAPLE S15°W 24.03'
  - NAIL & TAG IN W. SIDE R.R. TIE GATE POST EAST 58.65'
  - SOUTH FACE OF TRAFFIC SIGN NORTH 9.65'



Signed by *Raymond Moored*  
 Surveyor's Michigan License No. 26463

Date 12/13/96

GOVERNMENT CORNER HISTORY

SOUTH WEST CORNER, SECTION 31, T. 1 N., R. 14 W.  
SOUTH EAST CORNER, SECTION 36, T. 1 N., R. 15 W.

A-13/M-13

G.L.O (BROOKFIELD)	1827	80.00 SET POST LYNN 26 N69°E 86 BUTTERNUT 10 N14°W 78 1/2 MILE DIST EAST=2634.07 1/2 MILE DIST NORTH=2650.13'
MC DOUGALL		COUNTY SURVEYOR NOTES STONE MAPLE 8" SW 54' ELM 10" SE 56'
RATEKIN	1971	SECTION CARD FD 1" PIPE W/STONES & CROCKERY 30" MAPLE S 23.0' 8" MAPLE S40°E 29.7' ST. SIGN S80°E 9.4' 10' S OF FENCE LINE TO WEST R.R. TIE N70°E 38.5'