

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

ALLEGAN (County)	Located in:	Corner Code -##
1. Public Land Survey	T <u>1N</u> R <u>14W</u>	<u>B-1</u>
	T ___ R ___	<u>Cheshire Twp</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:53
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
James A. Blanton
FILED

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	15	14	13	12	11	10	9	8	7	6	5	4	3
7													
8	10	9	8	7	6	5	4	3	2	1			
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, Donald R. Pitts Jr., in a field survey on August 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Not set by Government
 Circa 1900-Allegan Co. Surveyor Notes
 1" Iron
 15" Oak N. 59.6'
 24" Oak S. 35.7'
 18" Oak S.E. 65.8'
 18" & 15" Twin Oak S.E. 96.2'
 1992-Allegan Co. Surveyor, Kirk L. Van Order
 Found 1" Iron
 Nail in E. Side 27" B. Oak S. 36.76'
 Nail in S.E. Side 11" B. Oak S.W. 85.64'
 Nail in N.E. Side 11" Cherry N.W. 47.66'
 Nail in S.E. Side 19" W. Oak N.E. 49.76'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1" Iron
 Nail in E. Side 27" B. Oak S. 36.76'
 Pulled Iron and set standard Allegan Co. Remon. 3/4"X24" Iron with Red Cap 23520
 Traversed 2639' East & 2390' West
 Approved by the Allegan Co. Remon. Peer Group on April 12, 1994. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. *Kirk L. Van Order*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Standard Allegan Co. Remon. 3/4"X24" Iron with Red Cap 23520
 B-13, T.2N., R.14W., Standard Allegan Co. Remon. 3/4"X24" Iron with Red Cap 23520 N. 76.07'
 Nail & Allegan Co. Remon. Tag S. side 14" Oak N. 55°W. 52.65'
 " " " " " " E. side 28" Oak S. 05°W. 36.75'
 " " " " " " S. side 22" Oak N. 40°E. 27.34'



Signed by *Donald R. Pitts Jr.* Date 30 August 1994
 Surveyor's Michigan License No. 25867

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983