

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

ALLEGAN <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>IN</u> R <u>14W</u>	B-13 CHESHIRE
SOUTH 1/4 COR.	T <u>   </u> R <u>   </u>	_____
SEC. 31, T1N, R14W	T <u>   </u> R <u>   </u>	_____
2. Property Controlling	T <u>   </u> R <u>   </u>	_____
in Section	S <u>   </u> T <u>   </u> R <u>   </u>	_____
3. Miscellaneous	S <u>   </u> T <u>   </u> R <u>   </u>	_____
Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	_____

97 JAN 22 PM 1:14  
**FILED**  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, RAYMOND MOORED, in a field survey on OCT, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

**APPROVED REMONUMENTATION CORNER**  
P.A. 343 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 10-8-96  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON FROM CORNER HISTORY. REPLACED WITH STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON & CAP. ACCEPTED POSITION AS CAREFUL & FAITHFUL PERPETUATION OF THE ORIGINAL CORNER. APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 10-8-96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.  
NAIL & TAG IN N.E. FACE 18" MAPLE N40°E 43.29'  
NAIL & TAG IN E. FACE 26" MAPLE S45°W 26.79'  
NAIL & TAG IN S. FACE R.R. TIE N55°W 76.36'  
N.W. COR. TELEPHONE PEDESTAL S45°E 41.34'



Signed by Raymond Moored  
Surveyor's Michigan License No. 26463

Date 12/13/96

GOVERNMENT CORNER HISTORY  
SOUTH CORNER, SECTION 31  
TOWN 1 NORTH, RANGE 14 WEST

B-13

G.L.O (BROOKFIELD)	1827	40.00 SET POST BEECH 16 N40°E 21 BEECH 6 N69°W 21
MC DOUGALL		COUNTY SURVEYOR NOTES DISTANCE FORM A-13 2634.72
MITCHELL	1979	SURVEY, SHOWS WITNESSES (1/2 MILE E. C-13 2630.24) ST SIGN N.N.E. 35.6' 36" MAPLE S.W. 30.0' 48" MAPLE N.E. 59.7
RATEKIN	1980	SECTION CARD FD 1/2" IRON, AS SET BY MITCHELL IN 1979 ST SIGN N.N.E. 35.6' 36" MAPLE S.W. 30.0' 48" MAPLE N.E. 59.7
RATEKIN	1980	SURVEY. SHOWS COR. & MITCHELL 1979 WITNESSES
WIGHTMAN MOORED	1987	SHOWS COR. ON SURVEY NO WITNESSES (1/2 MILE NORTH B-12 2617.37)