

CONVEY &
REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Allegan (County)	Located in: Cheshire	Corner Code # E-13
1. Public Land Survey	T 1 N R 14W	SW Sec 33
	T R	E-13
	T R	CHESHIRE
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

98 JAN 21 PM 1:18
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 Register of Deeds Stamp & File
 Number

FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Lenke, in a field survey on April 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	H
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 E-13 GLO
 80.0 Set post common to 32 & 33
 Beech 8 inch N 33 1/4 E 6 LINKS
 Beech 9 inch N 42 1/4 W 15 LINKS
 May 8th 1827
 Wm. Brookfield

E-13 LCRC Nov. 19, 1972 Liber 2 Page 40
 Denny Middleton
 Found 1" iron in tile in centerline of roads north, east and west.
 Street sign northwest 41.36' to centerline
 60 penny spike in west side of wild cherry, 6", in clump southwest 27.97'

E-13 Mitchell Surveys
 8" Ash W. SW - 57.0'
 Street sign N. NW - 65.8'
 Triple Ash S. SE - 21.8'

Act 132 survey Rec. Liber 820 Page 736 same witnesses as shown in LCRC L2 page 40 (August 21, 1972).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" dia. iron 0.8' below bituminous road. None of the witnesses shown above remained, therefore retraced survey recorded Liber 820 Page 736. Found 1 & 1/2" pipe as called for in survey at the 1/8" post. Angle on east side of section line at the 1/8" post is 180° 00' 59", distance north to #12 measures 1318.07' (rec.=1317.36"), distance south to E-13 measures 1318.22' (rec.=1318.30").

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed iron and set standard Allegan County monument (3/4" x 24" steel rod w/red cap #23520). Monument is 0.6' below surface of bituminous.
 Nail & Allegan Co. Remon Tag 1.55' above grade in SW side of 6" White Pine N 40° W 98.08'
 Combination street/stop sign N 10° W 69.13'
 Nail & Allegan Co. Remon Tag 0.75' above grade in SE side of 7" White Pine S 60° W 53.04'
 West post of street sign S 10° W 17.26'
 Monument is 1"± south of centerline of Baseline
 Monument is 1"± east of centerline of 44th

APPROVED REMONUMENTATION CORNER
 P.A.345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 6-10-97
 COUNTY REP. K.V.O.

Signed by Robert E. Lenke
 For SDI CONSULTANTS, LTD.

Date 12/31/97

Surveyor's Michigan License No. 40160

LIBR 0006 PAGE 033

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
 JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1992