

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
 For corners in

<u>ALLEGAN</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>1N</u> R <u>14W</u>	<u>F-1</u>
	T ___ R ___	<u>Cheshire Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:54
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

I, Donald R. Pitts Jr. in a field survey on September 10, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O.-Not set by Government

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No. Physical corner found
 Set Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 0.41' West of F-13, T.2N., R.14W. on Line with F-13 and E-13, T.2N., R.14W.
 Approved by the Allegan Co. Remon Peer Group on April 12, 1994, this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
 Traversed 2640' East & 2640' West

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. Richard L. Van Dine

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 East 0.41'
 F-13, T.2N., R.14W. Standard Allegan Co. 3/4" X 24" Remon Iron W/Red cap #23520
 Nail & Allegan Co. Remon Tag in S.W. Side 19" Oak N.40°W. 49.53'
 " " " " " " " E. Side 24" Oak N.05°W. 64.77'
 " " " " " " " E. Side Power Pole S.05°W. 53.01'



Signed by Donald R. Pitts Jr. Date 12 SEPT 1994
 Surveyor's Michigan License No. 25867

LIBER 0005 PAGE 010