

CONVEY &  
REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Allegan  
(County)

Located in: Cheshire Corner Code # F-13

- |                                    |   |   |   |   |     |             |
|------------------------------------|---|---|---|---|-----|-------------|
| 1. Public Land Survey              | T | 1 | N | R | 14W | S1/4 Sec 33 |
|                                    | T |   | R |   |     | ✓ F-13      |
|                                    | T |   | R |   |     | CHESHIRE    |
|                                    | T |   | R |   |     |             |
| 2. Property Controlling in Section | S |   | T |   | R   |             |
|                                    | S |   | T |   | R   |             |
| 3. Miscellaneous Property in Sec.  | S |   | T |   | R   |             |
|                                    | S |   | T |   | R   |             |

Register of Deeds  
ALLEGAN COUNTY, MICHIGAN

98 JAN 21 PM 1:19

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Robert E. Lemke, in a field survey on October 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
F-13 GLO Nov. 1910 Survey Notes Tech-Mac Report  
40.00 Set qtr. section post Iron & Tile Aug. 31, 1976  
Beech 20 inch N 67<sup>1/2</sup> E 65 LINKS 2624' from F-13 to G-13 Coordinate printout of Section break  
Beech 20 inch N 63<sup>1/2</sup> W 51 LINKS From D.A. Ratekin & Associates  
May 1827  
Wm. Brookfield

Witness card (1976)  
1/2" by 1" solid bar in tile  
PK Nail in NW side P. Pole S60°W 78.38'  
St. sign N40°E 37.38' to face  
NW Edge Tel. Outlet N45°E 49.16'  
CL Gravel Rd. N 8'W  
In CL E-W Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Did not find any evidence of the monument described above or it's accessories. The position of the corner was computed using the following procedure: Found F-12 & F-11 and measured 2638.39' between corners. Inverse between coordinates from Tech-Mac report showed distance to be 2638.43'. Used angle & distance from report 180°00'25" (F-12 \* F-11 \* F-13) with a distance of 2636.28 ft (F-12 to F-13) to reset F-13. F-13 and G-13 is shown as 2624 in notes dated Nov. 1910, current measure is 2622.50'.

And is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Allegan County witness monument ( 3/4" x 24" steel rod w/red cap #23520)  
0.4' below surface of road.  
Nail & Allegan Co. Remon Tag in Jack Pine N 40° E 100.30'  
Center of stop sign post N 30° W 66.88'  
Nail & Allegan Co. Remon Tag 1.0' above grade in Power Pole S 75° W 96.62'  
Corner is 8' (+/-) east of Centerline 43rd Street

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990

ALLEGAN COUNTY

DATE APPROVED 10-14-97

COUNTY REP. K.V.O.

Signed by Robert E. Lemke

Date 12/31/97

For SDI CONSULTANTS, LTD

Surveyor's Michigan License No. 40160

USER 0606 PAGE 034

FORM APPROVED BY MICHIGAN STATE OF PROFESSIONAL SURVEYORS  
JAN. 28, 1971 REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995