

REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Allegan (County) Located In: Cheshire Corner Code # G-13

1. Public Land Survey T 1 N R 14W SW Sec 34  
 T R G-13  
 T R CHESHIRE  
 T R

2. Property Controlling in Section S T R  
 S T R  
 S T R

3. Miscellaneous Property in Sec. S T R  
 S T R

Register of Deeds  
ALLEGAN COUNTY, MICHIGAN  
*Joseph A. C. [Signature]*

98 JAN 21 PM 1:19

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Robert E. Lenke, in a field survey on April 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	8		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 G-13 GLO County Surveyor Records Fieldnotes dated Nov. 1910 Witness Card A (no date)  
 80.00 Set post common to 33 & 34 August 9, 1875 J.W. Hicks show G13 as Stone. SE Cor Stone  
 Beech 5 inch N 40 1/2 E 12 LINKS Shows distance of 39.86(2630.76') between G-13 & H13 Witness Card B (no date) Maple 14" NE 35.0'  
 Sugar 15 inch N 51 W 31 LINKS Current measure is 2629.08 Maple 32" N45E 36.28' Maple 16" NE 63.0'  
 May 8<sup>th</sup> 1827 PP S80E 74.50' CL E&W Rd South 3' +/-  
 Wm. Brookfield PP S60W 76.34' Maple 30" N20W 68.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Stone with "x" per the 5 witnesses shown on witness card B.  
 And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set standard Allegan County monument ( 3/4" x 24" steel rod w/red cap #23520)  
 Nail & Allegan Co. Remon Tag 1.7' above grade in W side 32" Maple N 36° E 36.10'  
 Nail & Allegan Co. Remon Tag 0.6' above grade in N side of Power Pole S 58° E 74.32'  
 Nail & Allegan Co. Remon Tag 2.4' above grade in E side of 30" Maple N 18° W 68.58'  
 Nail & Allegan Co. Remon Tag 0.9' above grade in N side of Power Pole S 58° W 76.42'  
 Monument is 3'± north of centerline of Baseline  
 Monument is on CL of 42<sup>nd</sup>.

APPROVED REMONUMENTATION CORNER  
 P.A.345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 6-10-97  
 COUNTY REP. K.V.O.

Signed by Robert E. Lenke  
 For SDI CONSULTANTS,LTD

Date 12/31/97

Surveyor's Michigan License No.40160

USER 0006 PAGE 035