

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

| | | |
|---------------------------------------|--------------------------|----------------------|
| <u>ALLEGAN</u> (County) | Located In: | Corner Code #: |
| 1. Public Land Survey | T <u>1N</u> R <u>14W</u> | <u>H-1</u> |
| | T _____ R _____ | <u>Cheshire Twp.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1994 DEC 16 AM 9:54
 Register of Deeds Stamp & File Number
 ALLEGAN COUNTY REGISTER OF DEEDS
 J. C. [Signature]

FILED

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Donald R. Pitts, Jr., in a field survey on September 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O.-Not set by Government
 Allegan County Surveyor Notes; Stake and Stone, No Witnesses
 1992-Allegan County Surveyor Kirk L. Van Order
 Set Capped Iron
 - Nail in N.W. Side Power Pole S.W. 98.22'
 Nail in E. Side Power Pole S.E. 69.05'
 Nail in S.W. Side Wood Post N.W. 82.66'
 Nail in N.E. Side 11" Oak S.E. 111.89'
 Iron in Mon. Box E. 6.61'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
 Found 1/2" Iron with cap Kirk Van Order
 Found 5/8" Iron in Mon Box East 6.59'
 Nail in N.W. side Power Pole S.W. 98.22'
 Pulled Iron and Set Standard Allegan County 3/4" x 24" Remon Iron with red cap #23520 in Mon Box.
 Approved by the Allegan Co. Remon. Peer Group on April 12, 1994, this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
 Traversed 2641' East and 2641' West

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. Kirk L. Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Standard Allegan Co. 3/4" X 24" Remon. Iron W/Red Cap #23520 in Mon. Box.
 H-13, T.2N., R.14W. Standard Allegan Co. 3/4" X 24" Remon Iron W/Red cap #23520 in Mon. Box East 6.59'
 Nail & Allegan Co. Remon. Tag in N.W. Side Power Pole S.45°W. 98.25'
 " " " " " " " " S.W. Side Power Pole S.25°E. 69.12'
 S.E. Corner House Foundation N.20°W. 200.44'



Signed by Donald R. Pitts, Jr.
 Surveyor's Michigan License No. 25867

Date 21 SEPTEMBER 1994

FILE# 0005 PAGE 011