

REMONUMENTATION

APR 25 1995

COMMISSION
For corners in

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>ALLEGAN</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>1N.</u> R <u>14W.</u>	<u>J-1</u>
	T _____ R _____	<u>Cheshire Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:54
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
Joseph A. Pitts

FILED

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	14	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	29	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald R. Pitts Jr., in a field survey on September 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessions and/or subsequent restoration:

G.L.O.-Not set by Government
Circa 1900-Allegan Co. Surveyor Notes
Stone
W. Oak 12° S.E. 38
Maple S.W. 49.4

1983-Allegan Co. Surveyor Notes

Found 1 1/4" Pipe w/John Hunt cap in centerline of 112th Avenue +
Centerline 39th Street West 3+
E. End 18"X40' C.M.P. S.45°W. 33.3' E. Edge Stop Sign Post S.35°W. 39.5'
E. End 18"X40' C.M.P. S.40°E. 28.3' W. Edge St. Sign Post S.15°E. 38.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1/2" Iron in Mon. Box.
Pulled Iron and set Standard Allegan Co. 3/4" X 24" Remon. Iron W/Red Cap #23520 in Mon. Box.
Approved by the Allegan Co. Remon. Peer Group on April 12, 1994, this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
Traversed 2651' East & 2651' West.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED 4-12-94
COUNTY REP. Richard L. Pitts

C. Description of monument for corner and accessions established to perpetuate locating the position of the corner:

Standard Allegan Co. 3/4" X 24" Remon. Iron W/Red Cap #23520 in Mon. Box.
J-13, T.2N., R.14W. Standard Allegan Co. 3/4" X 36" Remon Iron W/Red Cap #23520 in Mon. Box East 7.77'
Nail & Allegan Co. Remon. Tag in S.W. Side 18" Oak S.35°E. 60.22'
" " " " " " W. Side 10" Red Pine N.10°E. 96.60'
" " " " " " S.E. Side 16" Maple S.30°W. 68.70'



Signed by Donald R. Pitts Jr. Date 21 September 1994
Surveyor's Michigan License No. 25867

USE 0005 PAGE 013