

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For corners in

ALLEGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>14W</u>	<u>K-1</u>
	T _____ R _____	<u>Cheshire</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1994 DEC 16 AM 9:54
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
James A. Bhatia
Register of Deeds Stamp & File Number
FILED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


I, Donald R. Pitts Jr. in a field survey on September 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O.-Intersect N. Boundary 9 links W. of post where set post cor. Sections 1 & 2
 W. Oak 24" S.45°E. 48 Links Do 16" S.21°W. 41 Links
 1877-Allegan Co. Surveyor
 Stone
 Oak S.W. 36.4 Maple S.E. 35'
 1973-Allegan Co. Surveyor, Donald A. Ratekin, L.C.R.C. Liber 2 Page 190
 Found Stone, set 1" Iron on North side w/top of Iron over "X" in stone
 Nail E. side telephone pole N.20°W. 28.96'
 8" Elm N.40°E. 60.32' 14" Oak S.15°E. 114.89'
 8" Pine S.55°E. 64.32' 1/2" Iron E. 6.64'
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Iron in Mon. Box.
 Iron in Mon. Box East 5.78'
 Pulled Iron and Set Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 in Mon. Box.
 Approved by the Allegan Co. Remon Peer Group on April 12, 1994, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 Traversed 2661' East & 2651' West

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-12-94
COUNTY REP. *Robt. J. Van Orden*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Standard Allegan Co. 3/4" X 24" Iron W/Red Cap 23520
 K-13, T.2N., R.14W. Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 in Mon. Box.
 East 5.78'
 Nail & Allegan Co. Remon Tag in W. Side 26" White Oak N.05°E. 73.12'
 " " " " " " S.W. Side 10" Oak N.30°W. 47.51'
 " " " " " " S.E. Side 16" Burr Oak S.60°W. 135.20'



Signed by Donald R. Pitts Jr. Date 12 Sept 1994
 Surveyor's Michigan License No. 25867

LIBER 0005 PAGE 014