

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ALLEGAN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>14W</u>	<u>K-2</u>
	T ___ R ___	<u>CHESHIRE</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

ALLEGAN COUNTY REGISTER OF DEEDS

97 JAN 22 2:11 PM

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	4	3	2	1							
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DONALD R. PITTS JR., in a field survey on DECEMBER 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GOVERNMENT SET POST
- PEPPERAGE 12" S71°W 9 LKS
- BEECH 12" N83°E 16 LKS
- OLD NOTES - STAKE
- 14" CHERRY SE 18.4'
- 16" MAPLE NE 35.6'
- 24" MAPLE ENE 65.4'
- 7' S OF CENTERLINE CULVERT

(CONTINUED ON REVERSE SIDE)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON W/CAP #30075
FOUND IRON 8.43' NORTH AND 1.66' E
ACCEPTED IRON W/CAP # 30075. PULLED IRONS AND SET STANDARD ALLEGAN CO. REMON 3/4" X 24"
IRON W/RED CAP # 23520
APPROVED BY THE ALLEGAN CO. REMON PEER GROUP ON OCTOBER 10, 1995, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 10-10-95
COUNTY REP. Phil S. Tomlinson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- STANDARD ALLEGAN CO. REMON 3/4" X 24" IRON W/RED CAP #23520
- NAIL & REMON TAG N. SIDE 8" WHITE PINE S80°E 25.74'
- NAIL & REMON TAG SE. SIDE 22" MAPLE N45°E 33.83'
- W END 36" C.M.P. N80°W 22.94'
- W END 36" C.M.P. N80°E 15.45'



Signed by Donald R. Pitts Jr. Date 20 December 1995
Surveyor's Michigan License No. 25867

USE#0005 PAGE 358

SHEET 1 OF 2

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

(CONTINUED FROM REVERSE SIDE)

ALLEGAN COUNTY REMONUMENTATION

A. DESCRIPTION OF ORIGINAL MONUMENTS AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

OLD NOTES - STONE & CROCK NO WITNESSES
JOHN HUNT SET IRON

21.4' S 88°W E. END 3' CMP

14.10' S88°E END 3' CMP

N70°E MAPLE TREE 28.60' IN LINE WITH FENCE TO EAST

1995 - BASIL J. ANDRESS

SET IRON WITH CAP #30075

BASED ON OLD NOTES & ANGLES AND DISTANCES.