

**SURVEY & REMONUMENTATION**

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners **SECTION .**

Allegan (County)	Located in: Cheshire	Corner Code # K-13
1. Public Land Survey	T 1 N R 14W	SE Sec 35
	T R	✓ K-13
	T R	CHESHIRE
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 98 JAN 21 PM 1:20  
 FILED  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Robert E. Lemke, in a field survey on April 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	13	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 K-13 GLO  
 80.00 Set post common to 35 & 36  
 Pine 30 inch N 88<sup>1</sup>/<sub>2</sub> E 80 LINKS  
 Pine 7 inch N 9<sup>1</sup>/<sub>2</sub> W 10 LINKS  
 May 1827  
 Wm. Brookfield

K-13 Witness card  
 3/4" pipe 2' above ground  
 24" Ash w/notch West 9.2'  
 Twin 32" Maple w/notch SE 10'  
 FE cor post 1' East  
 14" Ash w/notch NNW 19.3'

K-13 LCRC Nov. 8, 1974 Liber 2 Page 415  
 3/4" pipe  
 (1) 24" Ash w/notch West 9.2'  
 (2) Twin 32" Maple w/notch S45° E 10'  
 (3) FE cor post East 1.0'  
 (4) 14" Ash w/notch N 22° W 19.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1" (OD) pipe 2' above ground. Item 1 from L. 2, P. 415 is a 24" stump and measures 9.1' to face. Item 2 from L. 2, P. 415 remains and measures 9.9'. Item 3 from L. 2, P. 415 is gone. Item 4 from L. 2, P. 415 measures 19.3'.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Broke pipe flush with the ground and set standard Allegan County monument ( 3/4" x 24" steel rod w/red cap #23520) inside the remains of the 1" pipe.  
 Nail & Allegan Co. Remon Tag in W side of Maple S 42° E 10.46'  
 Nail & Allegan Co. Remon Tag in W side of 15" Ash N10° W 20.24'  
 Nail & Allegan Co. Remon Tag in E side of 8" Ash N 55° W 21.20'  
 Nail & Allegan Co. Remon Tag in E side of 12" Ash N 66° E 22.59'

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 6-10-97  
 COUNTY REP. K.V.O.

Signed by Robert E. Lemke  
 For SDI CONSULTANTS LTD

Date 12/31/97

Surveyor's Michigan License No. 40160

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS  
 JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT. 1995

1672 0006 PAGE 045