

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ALLEGAN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>14W</u>	<u>1-2</u>
	T ___ R ___	<u>CHESHIRE</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY
 97 JAN 22 AM 1:21
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	15	14	13							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DONALD R. PITTS JR., in a field survey on SEPTEMBER 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NOT SET BY GOVERNMENT

OLD NOTES - STONE & IRON
 MAPLE 26 SW 27.8'
 NE COR HSE SW 66.2'
 28" OAK SE 93.3'
 12" OAK NE 115.2'

1973 - DONALD A RATEKIN, CO. SURVEYOR
 L.C.R.C. LIBER 2, PAGE 191
 FOUND 1 1/4" SOLID IRON

(CONTINUED ON BACK OF CERTIFICATE)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON 1.17' NORTH AND 3.61' WEST OF INTERSECTION OF 1/4 LINES
 FOUND P.K. NAIL IN N. SIDE 40" MAPLE WEST 59.63'
 FOUND S.W. COR LARGE PHONE CABLE BOX N30° W 58.10'
 PULLED IRON
 SET STANDARD ALLEGAN CO. 3/4" X 24" REMON. IRON W/RED CAP # 23520
 APPROVED BY THE ALLEGAN CO. REMON. PEER GROUP ON OCTOBER 10, 1995. THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-16-95
 COUNTY REP. Donald R. Pitts, Jr.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD ALLEGAN CO 3/4" X 24" REMON. IRON W/RED CAP # 23520
 NAIL & REMON TAG N. SIDE 40" MAPLE WEST 59.63'
 NAIL & REMON TAG N.W. SIDE 36" OAK N70° E 100.61'
 NAIL & REMON TAG N. SIDE 24" OAK S80° E 129.27'
 S.W. COR LARGE TELEPHONE CABLE BOX N30° W 58.10'



Signed by Donald R. Pitts, Jr. Date October 13, 1995
 Surveyor's Michigan License No. 25867

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1979
 REVISED MAY 14, 1978
 REVISED JAN., 1983

USE: 0005 PAGE 360

SHEET 1 OF 2

(CONTINUED FROM FRONT OF CERTIFICATE)

- A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION.
- ST. SIGN N50E 29.92'
 - NE COR HOUSE S55W 66.15'
 - 34" OAK WEST 57.8'
 - 1/2" IRON W/CAP .S45E 45.99'
 - 1977 - DONALD A. RATEKIN, CO. SURVEYOR
FOUND IRON
NO WITNESSES
 - 1981 - DONALD A. RATEKIN, CO. SURVEYOR
FOUND IRON
SAME WITNESSES AS L.C.R.C.
LIBER 2, PAGE 191
 - 1984 - JOHN H. DILLINGHAM
FOUND IRON
NO WITNESSES
 - 1989 - WIGHTMAN MOORED, INC.
FOUND 1" IRON .
N.W. COR HSE FNDN WSW 89.17'
N.E. COR HSE FNDN SW 66.63'
S.W. COR LARGE PHONE CABLE BOX NW 58.10'
40" MAPLE WEST (P.K. NORTH SIDE) 59.93'
P.K. S.E. SIDE POWER POLE
W/METER & WEATHER HEAD N.E. 125.94'

RECORDED IN THE OFFICE OF THE CLERK OF THE SUPERIOR COURT
OF THE STATE OF CALIFORNIA
IN THE COUNTY OF SAN DIEGO
ON THIS 15th DAY OF JANUARY
1989 AT SAN DIEGO, CALIFORNIA
BY _____