

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ALLEGAN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>14W</u>	<u>I-4</u>
	T _____ R _____	<u>CHESHIRE</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

97 JAN 22 PM 1:21
 REGISTER OF DEEDS
 ALLEGAN COUNTY
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	12	11	10	9	8	7	6	5	4	3	2	1
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	32	33	34	35	36						
13												

I, DONALD R. PITTS JR. in a field survey on NOVEMBER 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:
 NOT SET BY GOVERNMENT
 OLD NOTES - STAKE
 30" MAPLE NE 33.5'
 GUY POLE NE 38.6'
 ST. SIGN NW 34.3'
 P.P. SE 38.3'
 P.P. SW 63.8'
 24" MAPLE SW 71.4'

(CONTINUED ON BACK OF CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND IRON & STAKE
 P.P. S55E 38.3'
 C.L. "X" 8'± & 5'± W
 PULLED IRON AND SET STANDARD ALLEGAN COUNTY REMON 3/4" x 24" IRON W/RED CAP # 23520 APPROVED BY THE ALLEGAN CO. REMON PEER GROUP ON OCTOBER 10, 1995. THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-10-95
 COUNTY REP. Donald R. Pitts Jr.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 STANDARD ALLEGAN CO. REMON 3/4" x 24" IRON W/RED CAP # 23520
 NAIL & REMON TAG IN W SIDE GUY POLE, N30°E 42.10'
 NAIL & REMON TAG IN NE SIDE POWER POLE S55°E 39.28'
 NAIL & REMON TAG IN NW SIDE GUY POLE S30°W 63.98'
 TOP CENTER OF UNDERGROUND TELE PEDESTAL S20°E 68.59'
 C.L. "X" 8'± N and 5'± W



Signed by Donald R. Pitts Jr. Date 21 November 1995
 Surveyor's Michigan License No. 25867

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

(CONTINUED FROM FRONT OF CERTIFICATE)
ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION.

- 1965 - DONALD A. RATEKIN, COUNTY SURVEYOR
FOUND IRON IN STAKE
NO WITNESSES
- 1970 - DONALD A. RATEKIN
FOUND IRON IN STAKE
NO WITNESSES
- 1984 - RAYMOND E. MOORED
UNRECORDED SURVEY NOTES CENTER OF SEC. NO WITNESSES OR NOTATION OF
PHYSICAL CORNER
- 1988 - WIGHTMAN MOORED, INC.
FOUND STAKE & IRON
40" MAPLE N30E 33.5'
GUY POLE N25E 38.7'
P.P. S55E 38.3'
P.P. S30W 63.9'
C.L. "X" 8± N & 5'± W
16" MAPLE S80W 77.7'