

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>14W</u>	<u>M-3 (SE, 1)</u> <u>CHESHIRE TWP.</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

1994 JAN -5 PM 4: 02
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
James W. Bette

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, BASIL ADDRESS in a field survey on DECEMBER 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. - NORTH ON EAST SIDE OF SECTION 12 80.00 CHS. SET POST CORNER SECTIONS 1 & 12.

COUNTY SURVEYOR'S OLD NOTES: STONE
WITNESS: MAPLE 12" SOUTH 15.7'
MEAS. NORTH 40.45 CHS. (2669.70') TO E 1/4 COR.

(CONTINUED ON BACK OF CERTIFICATE)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1" PIPE ON SOUTH SIDE OF STONE.
PULLED PIPE AND REPLACED STONE W/ STD. ALLEGAN CO. MON.

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 12-21-93.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED STONE W/ STD. ALLEGAN CO. MON. (3/4" STEEL PIN W/ REMON. CAP)
NAIL & REMON. TAG E SDE 14" WALNUT CLUMP SOUTH 55.36'
NAIL & REMON. TAG SE SDE 9" WALNUT SW 52.44'
NAIL & REMON. TAG E SDE 6" W. CHERRY NNW 135.86'
NAIL & REMON. TAG W SDE TWIN (10"-14") OAK NE 190.12'
C/L GRAVEL RD. (110th AVE) NORTH 14' +/-



Signed by Basil J. Address, Jr. Date 12-31-93
Surveyor's Michigan License No. 30075

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/ OR SUBSEQUENT RESTORATION.

1975 +/- D. A. RATEKIN, C.S.

1" PIPE S. SIDE OF STONE

WITNESSES: NAIL IN W. SDE 34" MAPLE SOUTH 14.30'
NAIL IN N. SDE 4" WALNUT S 50 W 25.30'
C/L RD. NORTH 14.0' +/-

1993 - WIGHIMAN MOORED

MEAS. WEST 2612.81' TO S 1/4 COR.