

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

FEB -1 AM 8-37

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T.1N... R.14W	M-12
EAST 1/4 CORNER SECTION 36, T.1N., R.14W. CHESHIRE TWP.	T..... R.....
	T..... R.....
	T..... R.....
2. Property Controlling in section	S.....T.....R.....
	S.....T.....R.....
3. Miscellaneous Property in Sec.	S.....T.....R.....
4. Lot No.....Recorded Plat.....		
5. Private Claims.....		

Joyce A. ...
REGISTER OF DEEDS
ALLEGAN COUNTY

REGISTER OF DEEDS STAMP & FILE NUMBER

LIBR00007 PAGE 179

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO
NORTH EAST SIDE SEC. 36, T1N R14W
40.00 SET QR SEC POST
BEECH 8 N17W 17
BEECH 16 S59W 33
- KIRK VAN ORDER, ACT 132 SURVEY, 9-16-97
7" CHERRY S.,SE 6.31'
12" ASH NW 20.72'
10" CHERRY W.,SW 23.08'
10" ASH N. 19.98'
- MOORED LAND SURVEYING, ACT 132 SURVEY, 9-17-97
FOUND 1/2" CAPPED IRON
M-12 WEST TO L-12 = N89°53'02"W 2587.20'
M-12 NORTH TO M-11 = N1°04'45" E 2644.87'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON (PS#19618) ON OCCUPATION LINE TO WEST PER WITS IN NUMBER (#2) ABOVE.
SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER.
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 14, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD 3/4" X 36" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
- NAIL IN W. SIDE 14" ASH N2E 19.99'
 - NAIL IN E. SIDE 10" CHERRY S10E 6.50'
 - NAIL IN NW SIDE 12" CHERRY S75W 22.90'
 - NAIL IN SW SIDE 14" ASH N25W 20.65'
 - FACE OF FENCE POST SOUTH 0.20'
 - IN LINE WITH FENCE TO WEST
 - A-12, T1N., R.13W. NORTH 30.49'

Raymond Moored
Date 12/24/99

Surveyors License No. 26463

