

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

98 JAN 21 PM 1:38 REGISTER OF DEEDS ALLEGAN COUNTY

FILED

For Corners in ALLEGAN COUNTY

Located In:

Corner Code #

Register of Deeds Stamp & File Number

- 1. Public Land Survey SEC. COR COMMON TO TIN, R13-14W TROWBRIDGE TWP. T..IN R..13W T...IN...R...14W... T..... R..... T..... R.....
2. Property Controlling in Section S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec. S..... T..... R..... S..... T..... R.....
4. Lot No..... Recorded Plat.....
5. Private Claims.....

A-13...TROWBRIDGE M-13...CHESHIRE

Grid table with columns A-M and rows 1-13. Contains numbers 1-36.

I, RAYMOND MOORED, in a field survey on SEPT. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED 11-11-97 COUNTY REP. K.V.D.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON WITH CAP IN MON. BOX PER WIGHTMAN MOORED WITNESSES FOR ROAD SURVEY. ALL WITNESSES REMAIN. SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON. BOX.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON 11-11-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP -FD. PK NAIL INW SIDE 11" ASH NNE 58.26' -FD. PK IN SE SIDE 21" ASH N20E 47.94' -FD. PK IN SE SIDE 14" MAPLE NE 71.13' -FD. PK IN NW SIDE 9" ASH SW 65.36' -FD. PK IN N SIDE 7" CEDAR S60W 73.32' -CL BLACKTOP SOUTH 0.5'+/-

Signature of Raymond E. Moored

Date 12/17/97

Surveyor's Michigan License No. 26463



GOVERNMENT CORNER HISTORY

SECTION CORNER COMMON TO TOWN 1 NORTH, RANGES 13 & 14 WEST
TROWBRIDGE & CHESHIRE TOWNSHIPS

A-13 & M-13

G.L.O. WM. BROOKFIELD, D.S. 1827
SET POST T1N, R13-14W
BEECH 14 N63E 30
BEECH 8 N64 1/4W 23

1989 WIGHTMAN MOORED ROAD SURVEY FOR ACRC. WITNESSED CORNER AND RESET
AFTER CONSTRUCTION.

PK W SIDE 11" ASH NNE 58.26'
PK SE SIDE 21" ASH N20E 47.94'
PK SE SIDE 14" MAPLE NE 71.13'
PK NW SIDE 9" ASH SW 65.36'
PK N SIDE 7" CEDAR S60W 73.32'
C/L GRAVEL ROAD SOUTH 3' +/-

1989 MITCHELL SURVEYS WITNESS SHEET - FOUND 1" IRON BAR

8" ASH SW 65.45'
8" ELM NNE 58.26'
12" MAPLE NE 71.20'

1992 WIGHTMAN MOORED BOUNDARY SURVEY

FD 1/2" IRON WITH CAP IN MON. BOX - NO WITNESSES

NO OTHER CORNER HISTORY AVAILABLE