

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION For corners in Allegan

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for County, Located In (Lee Township), Corner Code (A-13), and survey types (Public Land Survey, Property Controlling in Section, etc.).

1994 DEC 16 AM 9:54 REGISTER OF DEEDS ALLEGAN COUNTY MICHIGAN

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, George J. Mitchell, in a field survey on December 6, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 2-13, labeled TIN, R15W.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-13 1837 W. BROOKFIELD SET @ 80 CHAINS SUGAR MAPLE 24 N70-1/2E 18 LKS CHERRY 24 N75-2/3W 99 LKS 1890 - SURVEY BOOK - FD STONE MITCHELL 1989 - FOUND 5/8" IRON BAR POWER POLE NE 57.8' CK 1994 POWER POLE WNW 97.4' CK 1994 RATEKIN WITNESS CARD 1966 & 1987 FOUND IRON & WOOD STAKE POWER POLE ESE 57.63' CK 1994 POWER POLE WNW 97.4' CK 1994 STREET SIGN POST SSE 17.5' CK 1994 TELE CABLE BOX WSW 28.1' GONE 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-13 FOUND 5/8" IRON FROM ABOVE WITNESSES AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED 11-29-94 COUNTY REP. [Signature]



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-13 REPLACED IRON WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP. A.C. remon tag & nail in South side of Power Pole A2. 75° 57.78' A.C. remon tag & nail in West side of Anchor Post A2. 105° 60.28' A.C. remon tag & nail in South side of Power Pole A2. 275° 97.23' A.C. remon tag & nail in SE side of 40" Willow A2. 25° 90.34' Van Buren County Corner A2. 270° 120.79'

Signed by George J. Mitchell Date December 6, 1994 Surveyor's Michigan License No. 19618

LIBR 0005 PAGE 023