

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Allegan (County)	Located in:	Corner Code #
	Lee Township	
1. Public Land Survey	T 1 N R 15 W	B-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 1994 DEC 16 AM 9:54
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

I, George J. Mitchell in a field survey on December 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1 CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY

G. MITCHELL 1980 - SET 1" IRON ON TOWNSHIP LINE AT THE PRORATED GOVERNMENT DISTANCE.
 8" CHERRY N40W 26.2'
 8" MAPLE M45E 16.5'
 POWER POLE SSE 61.0'
 2588.94' WEST TO NW CORNER
 2643.80' EAST TO NE CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 FOUND 1" IRON THAT HAD BEEN SET ON THE TOWNSHIP LINE AT THE PRORATED GOVERNMENT DISTANCE BETWEEN A-1 AND C-1. THE CORNER LOCATION WAS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE CORRECT CORNER POSITION.

MEASURED 2588.50' WEST TO A-1 AND 2643.80 FEET EAST TO C-1

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-29-94
 COUNTY REP. Bob L. Van Orden



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 REPLACED IRON WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.
 A.C. remon tag & nail in South side of 8" Maple AZ. 47° 9.04'
 A.C. remon tag & nail in West side of Power Pole AZ. 190° 61.85'
 A.C. remon tag & nail in North side of 18" Cherry AZ. 270° 52.25'
 A.C. remon tag & nail in South side of 14" Cherry AZ. 310° 26.27'
 Clyde Township Corner B-13 AZ. 270° 197.28'

Signed by George J. Mitchell Date December 12, 1994
 Surveyor's Michigan License No. 19618

USE 0005 PAGE 024