

# SURVEY & REMONUMENTATION

## ALLEGAN COUNTY REMONUMENTATION

APR 25 1995

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**  
Allegan  
(County)

	Located In:	Corner Code #
	Lee Township	
1. Public Land Survey	T <u>1</u> N R <u>15</u> W	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 1994 DEC 16 AM 9:54  
 Register of Deeds Stamp & File Number

FILED

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**T1N, R15W**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George J. Mitchell in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessions and/or subsequent restoration:

B-13	1837 W. BROOKFIELD SET @ 40 CHAINS	MITCHELL 1989 FOUND 5/8" REBAR
	BIRCH 5 N67-1/2E 37 LKS	POWER POLE SE 78.9' CK 1994
	HEMLOCK 24 N40W 16 LKS	POWER POLE NW 53.9' CK 1994
		CENTER E-W ROAD SOUTH 2.0' CK94
		VAN BUREN COR WEST 191.80'


1989 MITCHELL MEASURED 2634.35 FEET WEST TO A-13 AND 2633.17 FEET EAST TO C-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 FOUND 5/8" IRON FROM ABOVE WITNESSES. IRON IS LOCATED ON THE BASELINE AT THE APPROXIMATE MIDPOINT BETWEEN A-13 AND C-13 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

MEASURED 2634.34 FEET WEST TO A-13 AND 2633.12 FEET EAST TO C-13

APPROVED REMONUMENTATION CORNER  
 P.A. No. #190  
 ALLEGAN COUNTY  
 DATE APPROVED 11-29-94  
 COUNTY REP. George J. Mitchell



C. Description of monument for corner and accessions established to perpetuate locating the position of the corner:

B-13	REPLACED 5/8" REBAR WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.	
	A.C. remon tag & nail in SE side of 6" Ash	AZ. 10° 49.30'
	A.C. remon tag & nail in SW side of Power Pole	AZ. 310° 52.49'
	A.C. remon tag & nail in SW side of Power Pole	AZ. 135° 83.67'
	Southeast corner of Mobile Home Fdtn slab	AZ. 325° 83.67'
	Van Buren County Corner	AZ. 270° 191.11'

Signed by George J. Mitchell Date December 6, 1994  
 Surveyor's Michigan License No. 19618

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983