

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION
For corners in
Allegan

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

| | | |
|------------------------------------|-------------------|---------------|
| (County) | Located in: | Corner Code # |
| | Lee Township | |
| 1. Public Land Survey | T 1 N R 15 W | C-1 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
 1994 DEC 16 AM 9:54
George J. Mitchell

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 15 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, George J. Mitchell in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1 L. LYON 1831 SET @ 80 CHAINS RATEKIN WITNESS CARD PD STONE
 HEMLOCK 10 S60E 17 LKS T. POLE SW 15.5' GONE 94
 HEMLOCK 8 N49W 28 LKS T. POLE SSW 14.6' GONE 94
 POWER POLE SW 52.0' CK 1994
 RATEKIN 1978 LCRC 1978 1" PIPE/STONE - MITCHELL 1980 PD 1" PIPE
 PWER POLE S15W 54.52 CK 1994 SAME AS RATEKIN 1978
 4" OAK S80E 13.1' CK 1994
 24" CHERRY S50E 133.40' CK 1994
 CLYDE CORNER WEST 197.43 CK 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 FOUND 1" PIPE OVER STONE 0.56 FEET NORTH OF TOWNSHIP LINE. SET CORNER ON TOWNSHIP LINE DUE SOUTH OF 1" PIPE AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

1" IRON PIPE WAS LEFT IN PLACE FOR REFERENCE PURPOSES

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-29-94
 COUNTY REP. *Keith A. Van Orman*



C. Description of monument for corner and accessories established to perpetuate locating the position of the

C-1 SET 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.
 A.C. remon tag & nail in East side of Power Pole AZ. 190° 54.94'
 A.C. remon tag & nail in SW side of 12" Oak AZ. 320° 25.50'
 A.C. remon tag & nail in SE side of 26" tw. Oak AZ. 00° 35.90'
 A.C. remon tag & nail in South side of 6" Oak AZ. 86° 24.16'
 Clyde Township Corner C-13 AZ. 270° 197.39'
 Center of North-South asphalt road AZ. 270° 98.0'

Signed by George J. Mitchell Date December 12, 1994
 Surveyor's Michigan License No. 19618

0005 PAGE 026