

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For Corners in
Allegan
(County)

	Located In:	Corner Code #
	Lee Township	D-1
1. Public Land Survey	T 1 N R 15 W	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:55
Register of Deeds Stamp & File Number
George J. Mitchell
REGISTER OF DEEDS
ALLEGAN COUNTY MICH

FILED

Register of Deeds Stamp & File Number

I, George J. Mitchell in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-1 CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY
RATEKIN 1978 SET 3/4" PIPE ON STRAIGHT LINE SPLIT BETWEEN C-1 AND E-1
POWER POLE S10E 44.78' CK 1994
8" ASH N10W 33.89' CK 1994
LCRC 1978 LIBER 3, PAGE 279

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
HOLLAND ENGINEERING - SAME AS ABOVE MITCHELL - SAME AS ABOVE

D-1 FOUND 3/4" ON TOWNLINE AND SPLIT BETWEEN C-1 AND E-1. THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEY. THIS MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION OF THE CORNER.
MEASURED WEST 2610.68 FEET TO C-1 & 2610.77 FEET EAST TO E-1

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-29-94
COUNTY REP. And S. Van Ouden



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-1 SET 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.
A.C. remon tag & nail in West side of Power Pole AZ. 170° 44.81'
A.C. remon tag & nail in NE side of Power Pole AZ. 133° 138.95'
A.C. remon tag & nail in SE side of Quad 8" maple AZ. 350° 33.12'
A.C. remon tag & nail in North side of 8" Poplar AZ. 257° 16.30'
Clyde Township Corner D-13 AZ. 270° 161.43'
Center of East-West Drainage Ditch AZ. 180° 14.0'

Signed by George J. Mitchell Date December 12, 1994
Surveyor's Michigan License No. 19618

LIBER 0005 PAGE 027