

**SURVEY
REMONUMENTATION**

APR 29 1999

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

.....ALLEGAN Located in: **.LEE Township** Corner Code #

FILED

1/28/1999 2:44:39 PM

- 1. Public Land Survey T..1..N R..15 WD-13.....
T..... R..... S1/4 POST, SEC 32
- 2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
- 3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
- 4. Lot No. Recorded Plat
- 5. Private Claims.....

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO 006 PAGE 59

I, **George J. Mitchell**, in a filed survey on **10/26 thru 11/07/98**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5					3		2			
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	10		20		21		22		23		24		
9													
10	30		28		26		27		28		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

W. BROOKFIELD 1827, WEST ON SOUTH SIDE OF SECTION 32, 40.00 CHAINS SET POST
MAPLE 15 N58E 60 LKS PINE 20 N49W 12 LKS

COUNTY SURVEYORS RECORDS 1966, FOUND STONE & PLACED IRON PIPE OVER
LYING ON SOUTH EDGE OF ROAD, IRON NORTH 33', FENCE LINE TO NORTH WEST 2'
2630.98 FEET EAST TO SE CORNER

G. MITCHELL P.S. 1998, FOUND 1" PIPE OVER STONE, C/L E-W ROAD NORTH 6 FEET
FD IRON NORTH 33' MEASURED 2631.09' TO SE CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13) FOUND 1" PIPE OVER STONE FROM CORNER HISTORY AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13) SOUTH QUARTER POST OF SECTION 32, TOWN 1 NORTH, RANGE 15 WEST

REMOVED 1" PIPE AND SET 3/4" X 24" IRON PIN WITH ALLEGAN CO. REMON CAP OVER STONE.

- A.C. REMON TAG & NAIL IN WEST SIDE 8" TRI MAPLE AZ. 010° 119.32 FEET
- A.C. REMON TAG & NAIL IN NW SIDE OF 10" PINE AZ. 080° 128.50 FEET
- A.C. REMON TAG & NAIL IN NE SIDE OF 30" ASH STUMP AZ. 275 113.35 FEET
- 1" PIPE AZ. 000° 33.06 FEET
- C/L OF EAST-WEST ROAD AZ. 000° 6.0'
- D-13 TO E-13 MEASURED 2631.09 FEET

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 10, 1998
COUNTY REP. [Signature]

Signed by George J. Mitchell Date Nov. 11, 1998
Surveyor's Michigan License No.19618.....

